


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
 Union National Bank Bldg, Wichita, Kansas.

SKELLY OIL COMPANY.  
 West Maxedon No. 1.

SEC. 25 T. 27 R. 11W.  
 Sec NW  
 330' fr E.L. 330' fr S.L.

Total Depth. 3457  
 Comm. 10-3-35 Comp. 10-29-35.  
 Shot or Treated. 2000 gal.  
 Contractor. Southern and Thurmond.  
 Issued. 12-28-35. Rotary 0 to 3421.  
 Cable 3421-3457

County. Pratt.



CASING.

12 1/2" 306' 65/8" 3417'

Elevation.

Production. 242 B. 24 Hr.  
 Est 150,000 Cu ft G.

Figures Indicate Bottom of Formations.

shaly shells and red bed	140
red bed and shale	347
shale	550
shale and shells	1050
salt	1270
shale and shells	1340
shale and lime shells	1690
lime	1710
shale	1815
shale and lime shells	2555
lime	2610
shale and lime shells	3126
lime	3140
shale and lime shells	3250
lime broken	3280
shale and lime shells	3413
cored 3413-3425 Rec. 4 1/2'	
Top 1' shelly lime and shale.	
Next 2' Brown fossiliferous lime	
last 1 1/2' Dense grey lime. No Sat. or porosity.	
Steel line correction 3425 equals 3417	
med hard brown and grey lime	
crystalline	3423
med hard brown and grey crystalline	
lime	3429
med hard brown and grey crystalline	
lime	3443
hard dark grey lime	3445
med soft grey lime	3451
showing 1 bailer free oil per hr	
med hard grey lime	3457
Total Depth	