

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

SKELLY OIL CO.
C. J. Moore No. 2.

SEC. 25 T. 27 R. 11W
CNL S $\frac{1}{2}$ S $\frac{1}{2}$ SW $\frac{1}{4}$
440' fr SL 1325' fr WL SW $\frac{1}{4}$

Total Depth. 3484'
Comm. 9-28-38 Comp. 10-24-38
Shot or Treated. 7000 Gals. 3440-3484
Contractor. Olson Drlg. Co.
Issued. 12-31-38 Rotary 3450
Cable 3484

County. Pratt



Elevation.

CASING:
13" 336'
7" 3440'

Production. Pot. 825 B.
Figures Indicate Bottom of Formations. 42,000 Gas.

sand, shells & shale	90
shale	686
salt & shale	810
grey shale & lime shells	1069
shale blue & shells	1323
lime	1337
shale	1339
anhydrite & shale	1496
anhydrite & lime	1521
lime	1618
lime & shale	1720
lime	1783
shale blue	1817
lime	2031
lime & shale	2185
sand	2206
lime & shale	2369
lime	2583
shale & lime	2638
lime	2695
shale & lime shells	2838
brkn lime	2862
lime	2952
shale & lime	3008
lime	3305
shale & lime	3409
shale	3424
cored 3424-36 rec 9'	
top 1' grey shaley lime	
2' red shaley banded lime	
btm 6' drk grey shale w/nodules of lime	
cored 3436-3450 rec 14'	
top 2' drk grey silty shale	
2' dense grey lime. No por.	
6' brown, por. foss. lime, good sat.	
btm 4' dense grey cryst. lime	
Top Lansing lime 3438	
Est. 5,000 cu ft gas	
cherty lime grey	3455
no sat. or por.	
grey & brown cherty lime	3460
no sat. or por.	
hrd grey cryst. lime, no shows	3467
cored w/CT 3467-3471 rec 4'	
all drk hrd cherty lime, no sat.	
cored w/CT 3471-3474 rec 1 $\frac{1}{2}$ '	
all hrd grey cherty lime, no sat.	
cored w/CT 3474-3477 rec 3'	
top 2' hrd grey cherty lime	
btm 1' brown cryst. lime, slight por., no sat.	
cored w/CT 3477-3484 rec 7'	
top 6' brown por., foss. lime, sat.	
btm 1' same, slight gas show & little sat.	
1000' OIH 7Hr. w/gas	
est. 3000 cu ft	
Total Depth	3484

Lansing Lime 3438-3484
Production after shot or acid
275 (flowed in 8-hr test)
Oil 3440-3484
Pay zone w/best pay 3440-46
and 3476-3484