


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SKELLY OIL CO.
C. J. Moore, No. 4

SEC. 25 T. 27 R. 11W.
CE $\frac{1}{2}$ SE SW
330' FEL 660' fSL SW $\frac{1}{4}$

Total Depth. 3484
Comm. 6-7-40 Comp. 6-28-40
Shot or Treated.
Contractor. Ruso Drilling Co.
Issued. 2-1-41

County Pratt.



CASING. Rotary 3430
Cable 3484

10 3/4" 373'
5 1/2" 3428 1/2'

Elevation.

Production. Pot. 540. 54B.

Estimated 5,000 gas.

Figures Indicate Bottom of Formations.

surface soil and sand	90	med. soft grey and brown	
red beds	265	crystalline limo	3460
shale and shells	373	little porosity and saturation.	
shale and shells	450	hard grey and brown crystalline	
red beds	520	limo	3465
shale	1000	Tested 5 hours, 1 barrel oil and	
salt	1175	no water.	
shale	1365	brown and grey crystalline	
lime	1560	limo	3470
shale	1605	Good porosity and sat. 500' OIH in 2 1/2 hours	
lime	1755	Gas estimated = 5,000 cu ft.	
shale	1845	brown and grey crystalline	
limo	2110	limo	3475
shale	2125	little porosity 1000' OIH in 5 hours.	
lime	2245	brown and grey crystalline limo	3480
shale	2380	little porosity.	
shale and lime	2525	brown and grey crystalline	
shale	2580	limo	3484
lime	2710	no porosity or sat.	
shale	2915	Total Depth.	
lime	2945		
shale	2980		
lime	3020	6-28-40 5000 gal	3470-3484
shale	3065	6-28-40 2000 gal	3435-3470
lime	3090		
shale	3170	Top Lansing lime	3424.
lime	3190		
shale	3228	Gas	3465-3470
shale and lime	3275		
shale blk	3397	3424-3430 slight porosity and stained	
shale dark grey	3410	Gas estimated 5,000 cu ft.	
lime porous dark	3414		
lime dark grey	3424	3450-3480 Main body pay formation.	
grey and brown crystalline			
and fossiliferous lime	3430	Initial prod. before acid. 1000' OIH	
slight porosity and stained.		in 5 hours.	
after cleaning out to bottom, tested		After acid. Flowed 8 hours 2" tubing	
3 hours, 3 gallons of oil and no wtr.		180.18 bbls oil. Established potential	
hard grey and brown crystalline		of 540.54 bbls., 5,000 gas.	
lime No porosity or Sat.	3436		
hard grey and brown crystalline			
lime	3450		