


SKELLY OIL COMPANY:
 D.E. Krehbiel No. 1.

SEC. 25 T. 27 R. 11W.
 SE NE NE
 440 fr E.L. 330' fr SL

Total Depth. 3470'
 Comm. 6-29-35 Comp. 7-30-35.
 Shot or Treated. 1000 gal acid.
 Contractor.
 Issued. 9-28-35

County. Pratt.



CASING.

12 1/2" 320' 7" 3422

Elevation.

Production. Pot. 155 B.
 est 80,000 G.

Figures Indicate Bottom of Formations.

sand	110
red bed	245
red bed sand & shells	345
red bed and shale	630
shale and shells	1030
salt and shale	1230
shale & lime shells	1885
lime and shells	1940
shale & lime shells	2000
lime	2025
shale & lime shells	2480
steel line Corr. 2480 equals	2486
shale and lime	2560
lime	2630
lime shells and shale	2680
lime	2755
shale and lime shells	2880
lime	2910
shale and lime	2950
shale and lime shells	2965
lime	2990
shale and lime shells	3115
lime	3125
shale	3140
shale and lime	3205
shale and lime shells	3315
steel line corr. 3315=	3327
lime and shells	3347
shale and lime shells	3395
steel line corr. 3395 =	3397
shale and lime shells	3405
lime and shale breaks	3417

cored 3417-3434 Rec. 5' 1st 1' Banded grey dolomite shale and lime
 next 1' Dense grey fossiliferous lime. Some porosity.
 Next 3' massive grey and brown lime with very porous streaks,
 slightly saturated.

Top of Lansing. lime 3426'

in 3 hour test bailed 10 gal oil with gas est. 5000 cu ft.

med hard grey lime with little grey shale 3435

med hard grey lime 3441 no porosity saturation.

med soft grey lime with

small amount brown lime 3446

saturation in brown lime

showed 1/2 bailer free oil in 2 1/2 hours.

while making run. No porosity or

saturation. 1st 3' hard next 3' soft.

hard grey lime and dark shale 3453

lime grey and brown 3459

brown and grey lime with

little dark shale 3465

1000' oil in hole. No increase gas.

lime soft grey 3468

No increase oil and gas

med hard brown and grey

lime 3470

No increase oil and gas.

Total Depth.

swabbed 2 hours 20 bbls oil and had swabbed
 to bottom, swabbed 7 times in 7 hours 17.44 bbls.

oil Lansing lime 3426

Main body pay formation pay 3456-3465.