

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SKEELY OIL CO.
East Maxodon No. 8

SEC. 25 T. 27 R. 11W.
CSL NE $\frac{1}{4}$
1320'fEL 330'fSL NE $\frac{1}{4}$

County Pratt.

Total Depth. 3464
Comm. 11-4-41 Comp. 11-24-41
Shot or Treated.
Contractor. Bodine Drilling Co.
Issued. 1-10-42

CASING. Rotary 3408
Cable 3464



35/8" 352' cemented.
5 1/2" 3407' cemented.

Elevation.

Production. Pot. 236B.

Formations Indicate Bottom of Formations.

sand	95	Before acid. 800' OIH
red bed	354	After shot POB 8 hours 78.66 bbls oil
red bed and shells	515	24% water to estb. 24 Hr pot. of 236 B.
red bed	650	
shells and shale	950	
salt	1100	
shale and shells	1180	
shale and lime	1390	11-25-41 7000 gal 3407-3464
lime	1485	
lime and shale	1580	
lime	1745	Top.
lime and shale	2050	Lensing lime 3403
shale and shells	2165	
shale and lime	2290	3408-3412 pay formation.
shale	2435	
shale and lime	2750	
broken lime	2990	
lime	3365	
shale	3405	
Buff fossiliferous lime	3410	

No porosity or sat.

Correction 3410 SLM Rotary
table equals 3408 SLM Derrick
shut down for 3 hours after cleaning out to
bottom and hole filled 150' with free oil
showing a little gas and no water.

Drilled

Dark grey crystalline lime
with little brown lime 3412 slight saturation and porosity
dark crystalline lime 3415 No saturation or porosity.
lime grey 3420 No saturation or porosity.
lime grey 3452

little porosity, and no saturation, 800' OIH in
20 hours while drilling.

CORED WITH CABLE TOOLS.

~~3452-3456~~ Rec 1'

All hard grey crystalline lime no porosity or sat.

DRILLED

lime grey with little dark shale	3456-3457	No porosity or sat.
lime grey with little dark shale	3460	little porosity
grey lime with 60% dark shale	3464	No porosity or saturation.

Total Depth.