

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - SKELLY OIL COMPANY
Farm - Fitzsimmons "A" No. 3

SEC. 35 T. 27 R. 11W

SW SE SW
330' fr SL, 1655' fr WL of
SW/4
County. Pratt

KANSAS

Total Depth. 3524
Comm. 10-31-48 Comp. 11-21-48
Shot or Treated. Acid
Contractor. Overland Drilling Co.
Issued. 2-26-49



CASING:

8 5/8" 398' cem w/250 sx.
5 1/2" 3506 1/2 SLM cem w/300 sx.
(8 5/8" OD set 4' in cellar & 5 1/2" cased to derrick floor. Production.
Figures Indicate Bottom of Formations.

Elevation. _____

POB 24 hrs, 80 oil,
no water.

surface soil, sand	85
redbed	255
shale, shells	398
shale	760
anhydrite	795
shale, shells	1085
salt	1230
shale, shells	1500
lime, shale	1575
lime	1845
sand	1880
lime	2170
shale	2570
shale, lime	2600
shale	2615
lime	2680
lime, shale	3135
lime	3240
lime, shale	3460
lime	3486
dense xlyn li: e	3517
lime porous	3520
SLM RTD	3516 1/2
lime gy oolitic	3519 1/2
lime gy, brwn	3524
total depth	

Tops:

Douglas Sand 3347
Lansing Lime 3482 1/2 SLM

3513 1/2 - 3516 1/2 good oil sat.
3519 1/2 - 3524 some stain & proosity.
3517 - 3520, good oil saturation.
Moved in and rigged up cable
tools and bailed hole dry Nov. 19,
5 1/2" casing tested OK. Drilled cement
plug and cleaned out to bottom.
Correction: 3520' SLM rotary table
equals 3516 1/2 SLM derrick floor.
Hole filled 2000' w/oil while
cleaning out.
3516 1/2 - 3519 1/2, no proosity.
3519 1/2 - 3524, some stained & porosity.
Producing formation: Lansing lime,
3513 1/2 - 3516 1/2.
Shot and acid: 11-22-48, w/3000 gals,
shot between 3506 1/2 - 3524'.