


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

SKELLY OIL CO.
A.J. Fitzsimmons No. 2.

SEC. 35 T. 27 R. 11 W
CE $\frac{1}{2}$ SW SW
660' f SL 990' f WL S $\frac{1}{2}$ SW $\frac{1}{4}$

County. Pratt

Total Depth. 3527'
Comm. 7-30-43 Comp. 8-21-43
Shot or Treated. 8-23-43 4000 Gals. 3488-3527
Contractor. Ruso Drlg. Co.
Issued. 10-9-43 Rotary O-3497
Cable 3497-3527



CASING:
8 5/8" 361' Cem.
5 1/2" 3488' Cem.

Elevation.

Production. Pot. 535 B., No Wtr
200 M.G.

Figures Indicate Bottom of Formations.

surface soil, shale, clay	0-80
sand	130
shale & red bed	220
red bed	450
shale	640
lime	680
shale	1395
lime	1625
shale	1645
lime	2050
shale	2115
lime	2325
shale	2365
lime	2490
shale & lime	2600
lime	2740
shale	2820
lime	3250
lime brkn	3340
lime sdy	3405
shale	3430
shale dk gy	3487
lime gy & brown foss., porous & oil stained	3492
lime gy & brown cryst., spotted porosity, no saturation	3497
lime gy, no sat. or por.	3503
lime gy	3508
lime gy & brown cryst, no sat. or porosity	3513
lime gy & brown cryst, rainbow sh oil	3519
no sample	3524
soft from 3520-24 1000' OIH in 1 hr & made head flow while plg blr	
lime gy & brwn cryst, little sat. & por.	3527
first 2' sft, last 1' hd well made two head flows while drlg	
Total Depth.	

Top Lansing Lime 3487

Pay formation 3488-92
Pay formation 3519-27