


GULF OIL CORPORATION.
 F.T. McClellan "B" No. 1

SEC. 36 T. 27 R. 11 W
 CN $\frac{1}{2}$ NW SW

Total Depth. 3541 P.B. 3510
 Comm. 10-13-41 Comp. 11-19-41
 Shot or Treated.
 Contractor.
 Issued. 3-28-42

County Pratt



CASING.

13" 383' cemented.
 8 5/8" 3468' cemented.
 7" 3513' cemented.

Elevation.

Production. Pot. 122 B.
 333 B. Wtr.

Figures Indicate Bottom of Formations.

cellar	10	Acidized
clay and sand	40	11-7-41 5000 gal.
sand and red rock	385	11-13-41 10,000 gal.
shale and red bed	490	
shale and shells	847	
shale and salt	1135	
sdy limo	1190	
anhydrite and shale	1280	
brokon lime and shale	1390	
anhydrite	1435	
anhydrite and broken limo	1469	
anhydrite	1625	
lime and shale	1810	
brokon lime	1928	
lime	1983	
lime and shale	2020	
brokon lime	2218	
brokon lime and shale	2280	
shale and limo shells	2430	
shale	2490	
shale and shells	2577	
shale and lime	2677	
shale and shells	2740	
shale and lime shells	2780	
shale	2955	
limo	2986	
lime and shale	3045	
brokon lime	3242	
limo	3313	
shale and lime	3360	
shale	3379	
shale and shells	3417	
limo	3432	
brokon lime	3455	
shale	3473	
limo	3475	
brokon lime	3476 ?	
red limo and red shalo	3478	
shale grey	3483	
limo grey	3489	
Lansing K.C. limo	3511	
lime	3541	
Total Depth.		
P.B. 3510		

Kansas City Lansing limo 3483-3510