

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - SKELLY OIL COMPANY
Farm - G. J. Miller No. 6

SEC. 36 T. 27 R. 11W
NE SE NW
330' fr EL, 990' fr SL NW/4

Total Depth. 3555
Comm. 2-22-49 Comp. 3-23-49
Shot or Treated. acid
Contractor. Charles Hulme Drilling Co.
Issued. 6-11-49

County. Pratt

KANSAS



Elevation. _____

Production. Dry

CASING:

8 5/8" 340' cem w/250 sx.
5 1/2" 3473' cem w/300 sx.

Figures Indicate Bottom of Formations.

surface soil, clay and sand	132	Remarks:
red bed, shells	330	3517-3524, 2 1/2 gals oil pr hr.
red bed, shale	340	5 1/2" casing perforated from 3110-28'
red bed	540	w/51 holes, 2904-40' w/108 holes,
shale, shells	860	2529'-50', 119 holes, 2090-2112', 21
shale	1160	holes.
salt, shale, shells	1400	
shale, lime	1470	
lime	1870	
shale	1880	
lime, shale	1945	
lime	2000	
lime, shale	2285	
shale	2710	
lime, shale	2735	
shale	2815	
lime, shale	2975	
lime	3005	
lime, shale	3220	
lime	3300	
lime, shale	3370	
sand fine grained micaceous slightly porous	3411	
sand, shale	3455	
lime, shale	3465	
lime drk gry to drab finely xlyn. RTD	3471	
Comm: 3471 SLM		
Bo. gry table = 3474 SLM OF		
lime drk gry xlyn	3478	
lime	3482	
lime hrd gry	3485	
lime lgt gry	3488	
lime gry	3493	
sand	3498	
lime drk gry	3504	
lime drk gry xlyn w/50%		
dark shale	3510	
lime lgt gry	3513	
sand	3517	
lime lgt fine gry	3524	
lime lgt gry	3531	
lime gry w/50% drk shale	3535	
lime lgt gry sdy	3539	
lime hrd drk gry	3543	
lime hrd gry	3555	
Total depth		

Tops:

Heebner shale 3254
Douglas sand 3370
Lansing lime 3468 SLM

ACID AND SHOT:

3-20-49, 4000 gals between 3474-3490'.
3500-3535' shell.
3-23-49, 4000 gals between 3495-3555'.
3-31-49, 1000 gals 2529-2550'.