

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER Driller date: 3-20-85

LEASE NAME L.E. Studer

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1 OWVO

LEASE OPERATOR Studer Oil Co.

ADDRESS P.O. Box 925 Pratt, Ks. 67124

PHONE# (316) 672-7572 OPERATORS LICENSE NO. 9582

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

       Ft. from S Section Line

       Ft. from E Section Line

SEC. 8 TWP. 24S RGE. 12 XXJ or (W)

COUNTY Pratt

Date Well Completed 1-22-86

Plugging Commenced 6-14-90

Plugging Completed 6-19-90

The plugging proposal was approved on June 18, 1990 (date)

by Steve Durant--Steve Pfeifer on location. (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached?       

Producing Formation Mississippian Depth to Top        Bottom T.D. 4480

Perfs: 4140-60 PBTID 4177'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	287	10 3/4	287	0
				4 1/2		52 fts. of casing.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from        feet to        feet each set  
Dumped sand to 50' above perfs and 4 sx. cement. Cut and pulled 52 fts. of 4 1/2 "  
casing. Top hole plug: 6-19-90: 400# hulls, 15 sx. gel, 60 sx. cement, 13 sx. gel,  
100# hulls, 10 3/4 wiper plug, 175 sx. cement on top. 60-40 poz, 6 1/2 gal. Max. pressure  
125#, ISIP 50#  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Studer Oil Co. JUN 20 1990

STATE OF Kansas COUNTY OF Pratt, ss. CONDON, JEFFREY D.

Judy Berry

plugging contractor

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.



(Signature) Judy Berry

(Address) Box 847 Pratt, Ks.

SUBSCRIBED AND SWORN TO before me this 16th day of June, 19 90

My Commission Expires: February 6, 1993