


NW NW SW  
 330' fr NL & 330' fr WL SW/4

County Pratt **5-27-12W**

KANSAS



Total Depth. 4304  
 Comm. 11-2-52 Comp. 11-29-52  
 Shot or Treated.  
 Contractor. Chas. Hulme Drlg. Co.  
 Issued. 3-7-53

Elevation. 1880 DE

Production. Dry

**CASING:**

8 5/8" 452' cem. w/250 sx  
 5 1/2" 4297' cem. w/200 sx

Figures indicate Bottom of Formations.

surface soil & sand	180	Pinhole porosity and some
red bed & shale	452	vugular poro. good odor
red bed	500	and free oil in wet sample
red bed & shale	685	4162-4183'
shale & shells	1260	no shows 4295-4300'
salt & shale	1700	No shows 4298-4301'
lime	2170	no shows 4301-4304'
lime & shale	2410	
lime	2530	DST: 4146' used 37' of
shale & shells	2595	anchor, open 1 hr. gas
lime & shale	2925	to surface in 23 mins. good
lime	3010	blow for 1 hr. rec. 65' of
shale & lime	3100	gas cut mud BHP 1160#.
lime	3250	
lime & shale	3340	11-30-52 Shot between
lime	3395	4252-4256'
shale	3440	12-4-52 Shot between
lime	3600	4222-4238'
shale & lime	3665	12-9-52 Shot 1500 qts.
lime	3782	between 4143-4183'
fine xyln lime	3786	
lime	3844	Ran Lane-Wells Gamma Ray
oolicastic lime	3849	Survey.
lime	3888	
fine xyln lime	3896	
lime	4110	
lime & chert	4162	
tripolitic chert	4183	
lime & chert	4202	
shale	4220	
cored from	4220-4263'	
cored from	4263-4270'	
shale & lime	4293	
lime	4295	
tan, fine sucrosic to		
fine xyln dolo.	4300	Pin hole to oolicastic poro.
SIM 4300		spotty brown oil stain
gry xyln dolo	4304	3782-3786'
Total Depth		Spotty brown oil stain &
		dead oil 3844-3849'
		Pinhole and oolicastic poro.
		spotty brown oil stain, probably
		dead oil 3888-3896'
Tops:		
Brown Lime	3664	
Lansing Lime	3678	
Miss. Lime	4118	
Viola Lime	4142	
Simpson Shale	4196	
Simpson Dolomite	4208	
Simpson Sand	4224	
Arbuckle Lime	4290	