

25-27-12W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING COMPANY
Farm- Barnes No. 1


SEC. 25 T. 27 R.12W
NE NE SW

Total Depth. 4430
Comm. 11/6/51
Shot or Treated.
Contractor.
Issued. 10/11/52

Comp. 12/2/51

County Pratt

KANSAS



CASING:
8 5/8" 370' 250 sx cement
5 1/2" 4430' 250 sx cement

Elevation. 1753 RB
1751 CM

Production. dry

Figures Indicate Bottom of Formations.

sand-shale-shells	370
red bed	580
shale-sand-shells	660
shale-red bed-shells	1093
shale-salt-shells	1532
shale & shells	1630
lime & shale	1730
shale & shells	1950
shale-sand-lime	2097
shale & lime	2526
shale & lime streaks	2720
shale-lime-sand	2809
shale & lime	3140
shale-lime-sand	3238
lime & shale	3425
shale & sandy lime	3503
shale & lime	3715
shale-lime-sand	3746
lime & shale streaks	3791
lime	3820
lime & shale	4008
lime & chert	4018
lime	4024
lime & chert	4050
chert	4078
chert & shale	4125
shale & lime	4204
shale & chert	4240
chert-lime-shale	4245
cherty dolomite	4255
chert & shale	4275
shale & lime streaks	4295
shale	4305
shale & sandy lime	4325
shale & sand	4360
sand	4363
sand-shale-lime	4381
shale	4411
shale & lime	4430 T. D.

Total Depth

Tops:

Brown Lime	3562
Gray Lime	3582
Mississippi	4002
Miss. (Trip.)	4031
Kinderhook	4122
Viola	4230
Simpson Shale	4302
Simpson Dolo.	4305
Simpson Sand	4324
Arbuckle	4421