

25-27-12W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- HAMILTON BROS. & ANSCHUTZ
Farm- Barnes No. 3

SEC. 25 T. 27 R. 12W
NE NW SW

Total Depth. 4445'
Comm. 4-2-52
Shot or Treated.
Contractor.
Issued. 5-7-55

Comp. 5-14-52

County Pratt
KANSAS



CASING:

13" 110'
8 5/8" 810'
5 1/2" 4326'

Elevation. 1760 KB

Production. Dry

Figures indicate Bottom of Formations.

SAMPLE LOG

3638-50 brwn lime-gry lime
w/scattered stain
3712-20 Slightly por. brwn.
& gr lime w/good
stain to Sat. good
odor.
3733-40 Same as above w/tr
chert.
3750-60 gry non-por. lime
w/very slight stain-
ing.
3810-25 Slightly stained in
vuglar poro. gry
lime & slightly poro.
ool. lime
3840-3850 Same as above
3880-85 Brwn. xlym lime
w/slight stain in
vuglar poro. pieces.
3910-15 Brwn & gry slightly
poro. lime & tr. chert.
Scattered staining in
poro. pieces.
4018-25 White chalky sft. lime
w/blk oil stain. Some
gry. lime & vari. col.
shale & tr chert.
4065 Cir. for samples-lime &
chert w/stain, no odor.
4080 Cir. for samples wh.
milky chert, & some trip.
chert w/good stain. No odor.
4088 Cir. same as above.
4240-68 Cherty dolo. w/sl. stain &
odor in we samples.
4340-50 sand w/slight stain & odor.
Total Depth

5 min. good blow thruout test. Rec. 115'
gas cut mud. BHP 1345# 15 min.

4334-40 Open 1/2 hr. Rec. 6' mud BHP 0#
4335-50 Open 1 hr. Rec. 2550' gas 230'
thin foamy muddy wtr. , & 1320'
salt wtr. BHP 1290# IFP 60#
FFP 660# Shut in 15 min.

TOPS:

Brown Lime	3581
Lansing	3600
Mississippi	4054
K.nderhook	4176
Viola	4239
Simpson Shale	4332
Simpson Sand	4338
Arbuckle	4439

DST 3712-40 open 1 hr. rec. 235' muddy
salt wtr. BHP 1200#, IFP 45#
FFP 110#, shut in 15 min.
DST 4055-65 Open 1 hr. rec. 30' mud BHP
150# 15 min.
DST 4065-68 Open 1/2 hr. Rec. 30' mud BHP
0#
DST 4244-68 Open 1 hr. gas to surface in