

FARM Beck "B"

NO. 2

API 15-151-10183

6-27-12W

TOTAL DEPTH 4264 1/2 DF

COMM. 3-5-51

COMP. 3-28-51


SHOT OR TREATED

CONTRACTOR Coop. Refg. Assoc.

ISSUED 4-14-51

COUNTY Pratt

KANSAS



CASING

8 5/8" 436' cem. w/300 sx  
5 1/2" 4218 1/2' cem. w/175 sx

ELEVATION 1874 DF

PRODUCTION Flowed 475.96 BO  
NW

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil	25
sand	30
clay	55
sand	160
red bed & shells	436
red bed & shale	740
shale	1275
anhydrite	1285
shale & shells	1725
lime	2465
shale & shells	2475
shale & lime	3245
lime	3500
lime & shale	3625
lime	3990
lime & shale	4025
lime	4243
simpson sand	4268 1/2

RTD 4268 1/2 = 4264 1/2 D.F.  
Total Depth

Tops: D.F.	
Heebner	3450
Brown Lime (Iatan)	3669
Lansing-Kansas City	3689
Mississippian	4071
Kinderhook	4098
Viola	4111
Simpson shale	4190
Simpson dolomite	4207
Simpson sand	4218

Drilled plug.  
 Ran tubing. Flowed through tubing.  
 Cleaned out.  
 Flowed 112 BO in 2 1/2 hrs.  
 Hooked up well.  
 Flowed 95 BO in an hr. through 3/4 in. choke.  
 In 24 hrs. flowed 475.96 BO through 2 1/4" choke. Casing pressure 300#. Tubing pressure 150#.

ASSOC