

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 7 T. 27 R. 12W

FARM Deistler

NO. 2

LOC. NW SE NE

825' N, 990' W of E/4 Cor.

TOTAL DEPTH 4290 PB 4287

COMM. 10-3-50

COMP. 11-9-50

SHOT OR TREATED

CONTRACTOR Holm Drlg.

ISSUED 1-13-51

COUNTY Pratt



CASING

8 5/8" 404' cem. w/275 sx.
5 1/2" 4237' cem. w/200 sx.

ELEVATION 1883

PRODUCTION flowed 81 oil
no wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

sand & clay	100
shale & shells	225
red bed	750
shale	900
anhyd.	925
shale	1730
lime, shells & shale	1885
lime & shale	2405
shale	2630
lime & shale	3330
lime	3345
lime & shale	3845
lime	4120
lime & chert	4152
lime, chert & shale	4215
lime	4241
4241 RTD. = 4238 SL ^M	
sand	4289
shale	4290
Total Depth	
Plugged back to	3287
Tops: Corr:	
Lansing	3705
Mississippi	4120
Simpson shale	4211
Simpson dolo.	4233
Simpson sand	4239

Penetration 51'

Laded hole w/2500' wtr.

Show oil 4239-4266

Bailed 12 gals. oil per hr. for 13

hrs. at 4266 Deepened 4266-71

bailed 16 gals. oil per hr. for 7 hrs.

11-2-50 Az 500 gals., no increase in oil

Deepened 4271-80 1560' oil in 6 hrs.

10 mins. at 4278-80. 1690' oil in 7 hrs. 5

mins. at 4280

Swabbed 30 oil, no wtr, 15 hrs.

11-9-50 Deepened 4280-90

Shot 40 qts. 4254-82 Cleaned out to 4287.