


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL COMPANY  
Farm- Luders "B" No. 4

SEC. 7 T. 27 R. 12W  
SE SE SW  
330' fr EL 330' fr SL SW/4

Total Depth. 4284 PB 4195  
Comm. 10-30-52 Comp. 11-22-52  
Shot or Treated.  
Contractor. Claude Wentworth Drlg. Co.  
Issued. 4-18-53

County Pratt KANSAS



CASING:  
8 5/8" 449' cem. w/250 sx  
5 1/2" 4283' cem. w/200 sx

Elevation. 1852 DF  
SCC  
Production. Pot. 143 BO

Figures indicate Bottom of Formations.

sand & clay	85
red bed & sand	200
red bed & shells	645
lime	655
shale & shells	1300
salt & shale	1425
shale & shells	1630
lime & shale	2300
lime	2395
lime & shale	3115
lime	3190
lime & shale	3540
lime	4035
lime & shale	4167
lime & sand	4224
cored from 4224-4247' rec.	
23'	
Cored from 4247-4265'	
rec. 18'	
cored from 4265-4284' rec.	
18'	
shale	4284
Total Depth PB	4195

Tops:  
Brown Lime 3654  
Lansing Lime 3672  
Mississippi Lime 4110  
Viola Lime 4154  
Simpson Shale 4200  
Simpson Dolomite 4211  
Simpson Sand 4226

Producing Formation:  
Viola Lime 4154-4176'

12-11-52 shot between  
4225-4237' hydrafrac  
12-20-52 shot between  
4270-4274' hydrafrac  
12-23-52 shot between  
4250-4258' hydrafrac

4154-4176' good por.  
fair to ggod sat.