


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL COMPANY
Farm- J. B. Brown No. 2

SEC. 18 T. 27 R. 12W
NW NW NW
330' fr NL 330' fr WL NW/4

Total Depth. 4306 PB 4301
Comm. 11-22-52 Comp. 12-9-52
Shot or Treated.
Contractor. Chas. Hulme Drlg. Co.
Issued. 2-14-53

County Pratt
KANSAS



Elevation. 1866 DF

Production. Pot. 3000 bbls.

Figures indicate Bottom of Formations.

sand	130	Traces of free oil and odor
red bed	250	in wet samples 4227-4250'
shale & shells	450	
red bed	735	Producing Formation:
salt	975	Simpson Sand 4269-4281'
shale & shells	1200	
shale & lime	1840	12-17-52 shot between
lime	1970	4269-4281'
shale & lime	2610	
shale & shells	2780	
shale & lime	3175	
lime	3565	
lime & shale	3745	
lime	3800	
fine oolitic lime	3803	
lime	3853	
oolitic lime	3858	
lime	3862	
oolitic lime	3864	
lime	3890	
porous xyln vugular		
lime with strks of		
oolitic lime	3900	
lime	3907	
oolitic & oolitic		
lime	3911	
lime	4097	
chert & lime	4167	
chert	4212	
chert & lime	4227	
sand & sandy lime	4229	
lime	4250	
cored from 4250-4306'		
Total Depth PB 4301	4306	

Logs:

Brown Lime	3678
Mansing Lime	3693
Miss. Lime	4133
Viola Lime	4176
Simpson Shale	4218
Simpson Dolomite	4231
Simpson Sand	4250

Traces of brown oil stain
3800-3803'
Brown oil stain and dead
oil 3853-3858'
Brown oil stain and dead
oil 3862-3864'
Traces of brown oil stain
and dead oil some odor
3890-3900'
with brown oil stain and
dead oil some odor 3907-3911'