


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm- M. D. Burkner No. 6

SEC. 18 T. 27 R. 12W
NW NW SW
330' fr NL 330' fr WL SW/4

Total Depth. 4345 PBTD 4317
Comm. 6-30-53 Comp. 7-19-53
Shot or Treated.
Contractor. Claude Wentworth Drilling Co., Inc.
Issued. 10-3-53

County Pratt
KANSAS



CASING:

8 5/8 @ 762' w/ 425 sx cem.
5 1/2 @ 4345' w/ 200 sx cem.

Elevation. 1890 DF

Production. Pot. 127.74 BO

Figures indicate Bottom of Formations.

surface soil & clay	10
sand	125
sand & red bed	245
red bed & shale	499
shale & shells	740
anhydrite	762
shale & lime	2890
lime	3499
lime & shale	3644
lime	3828
lime & shale	3872
lime & chert	3887
lime	3891
lime & chert	3907
lime	3981
lime, chert & shale	4291
cored: rec. 54'	4345
Total Depth	

TOPS:

Heebner	3533
Brown lime	3709
Lansing	3728
Base KC	4067
Marmaton	4081
Conglomerate	4140
Mississippi	4159
Viola	4217
Simpson shale	4264
Simpson dolomite	4275
Simpson sand	4292

Ran Gamma Ray Survey

Perf. 4325-30 w/ 30 holes: B & T 16 hrs.
20 BO, 20 BW, B & T 4 hrs, BO, 6 BW
Perf. 4300-05 w/ 30 holes B & T 10 hrs.
1 quart OPH
Sand-Oil-Frac 4300-05
Perf. 4292-96½ w/ 23 holes. Swbd 10 hrs.
124 BO, 41 BW. Swbd. 18 hrs., 98 BO,
33 BW. Swbd 6 hrs. 45 BO, used in
treating, 11 BW