

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- SKELLY OIL CO.
Farm- M. D. Burkner "A" No. 7

SEC. 18 T. 27 R. 12W
SE NW SW
1035' fr NL, 980' fr WL, SW/4

Total Depth. 4328 PBD 4327
Comm. 7-27-53 Comp. 8-13-53
Shot or Treated. Sand-Oil Frac 4289-4308½
Contractor. Claude Wentworth Drilling Co., Inc.
Issued. 11-6-54

County Pratt

KANSAS



CASING:

8 5/8 @ 803' w/ 450 sx cmt.
5 1/2 @ 4328' w/ 200 sx cmt.

Elevation. 1882 DF

Production. Pot. 3000 BO

Figures Indicate Bottom of Formations.

surface clay & sand	140
red bed	365
shale & red bed	660
sandy lime & anhydrite	675
red bed & shale	780
broken lime & anhydrite	803
shale & shells	1440
shale, salt & shells	1730
lime & shale	2115
shale & shells	2270
lime & shale	2520
lime & shale breaks	2665
shale & shells	2810
lime & shale	3215
lime & shale breaks	3285
lime	3883
broken lime	3953
lime & shale	3968
lime	4058
lime & shale	4093
lime	4167
shale & chert	4190
lime	4200
chert	4240
lime	4274
cored (rec. 47')	4328
Total Depth	

TOPS:

Heebner	3526
Brown lime	3700
Lansing	3718
Base KC	4058
Marmaton	4070
Conglomerate	4134
Mississippi lime	4155
Viola lime	4206
Simpson shale	4253
Simpson dolomite	4268
Simpson sand	4283

Perforation: 57 holes 4289-4308½
36 holes 4298½-4304½
24 holes 4304½-08½

Shot-8-25-53 -4289'-4308½'-Halliburton.
Sand-oil-Frac.

Prod. formation:
Simpson sand 4289-4308½'
oil 4289-4308½'