

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SKELLY OIL COMPANY
Farm. Gustave Seidel No. 1

SEC. 18 T. 27 R. 12W
NW NW NE
330' fr NL 330' fr WL NE $\frac{1}{4}$

Total Depth. 4297 PB 4292
Comm. 9-17-52 Comp. 10-4-52
Shot or Treated.
Contractor. Claude Wentworth Drlg. Co.
Issued. 11-22-52

County Pratt KANSAS



CASING:
8 5/8" 454' cem. w/250 sx
5 1/2" 4296' cem. w/200 sx

Elevation. 1853 DE

Production. 3000 BO

Figures Indicate Bottom of Formations.

surface soil & sand	90
red bed & sand	170
red bed & shells	454
red bed	620
lime, shells	635
salt & shale	780
shale & clay	1010
anhydrite	1045
shale & shells	1775
shale & lime	1860
lime, shells & shale	2060
lime broken & shale	2120
sandy lime	2160
lime & shale	3230
lime broken	3260
lime	3330
lime & shale	3470
lime	3490
lime & shale	3595
lime, shale & sand	3635
lime & shale	3680
lime	3846
oolicastic lime	3848
lime	3856
oolicastic lime	3861
lime	3891
fine xyn lime	3896
lime	3933
fine xyn lime	3936
lime	4065
lime & chert	4204
shale	4222

10-17-52 shot between
4248-4270'

Producing Formation:
Simpson Sand 4248-4270'

cored from 4222-4280' rec
58'
cored from 4280-4297' rec.
17'
Total Depth 4297
PB 4292

Tops:
Brown Lime 3660
Lansing Lime 3678
Miss. Lime 4110
Viola Lime 4156
Simpson Shale 4205
Simpson Dolomite 4218
Simpson Sand 4232

Brown stain and dead oil
3846-3848'
Brown stain and dead oil
3856-3861'
Spotted brown oil stain
3891-3896'
Dark brown stain, possibly
dead oil 3933-3936'