


ATLANTIC REFG.
Runyan No. 1.

11-27-13W 107/0
SEC. 11 T. 27 R. 13W
SW NW NE

Total Depth. 4437' P.B. 4297'
Comm. 5-20-37 Comp. 10-11-37
Shot or Treated.
Contractor, Parker Drlg. Co.
Issued. 10-30-37

County. Pratt

OCT 30 1937



Elevation.

CASING:

12 1/2" 241' 8"
8 5/8" 3920'
7 " 4288'
5 1/2" liner 114' at 4333'

Production. Pot. 397 B.O.

Figures Indicate Bottom of Formations. 2,000,000 Gas.

cellar	14	lime	3945
sand	40	lime grey	3950
shale grey	60	lime grey sft	3961
sand H.	75	lime grey hrd	3965
sand, gravel, wtr	115	lime	3973
shale	160	lime grey	4024
brkn sand, shale	195	shale blk	4030
red bed	325	lime brown sh oil	4032
sdv shale	350	lime grey	4037
shale	400	shale blue	4045
lime, shell, shale	460	lime grey	4048
red bed	590	lime brown hrd	4052
lime shells, shale	675	conglomerate	4060
shale	730	lime grey	4082
anhydrite	762	shale blue	4089
shale & anhyd. shells	1130	lime grey	4097
shale	1180	lime brown	4100
shale & lime shells	1406	lime grey	4113
shale & salt	1480	lime grey hrd	4127
shale & shells	1520	shale green	4130
shale	1582	lime grey hrd	4149 1/2
lime	1590	4149 1/2 equals 4163 1/2	
shale	1660	lime grey	4166
sdv shale	1700	red rock	4179
shale & lime shells	1820	shale red	4200
shale	1850	lime white	4226
shale & lime shells	2010	shale green	4238
brkn lime & shale	2060	lime grey	4280
shale, sand & lime shells	2160	shale	4293
brkn shale & lime "	2185	lime brown	4299
shale, sdv lime shells	2200	lime grey	4300
sdv shale	2250	shale blue	4309
brkn lime & shale	2305	lime grey	4310
shale	2325	lime	4311
brkn lime & shale	2340	sand	4333
lime	2364	shale green	4353
brkn lime & shale	2506	shale	4363
lime & shale	2566	shale green	4369
shale & lime shells	2807	shale	4372
shale	2850	shale green	4393
lime	2860	lime	4394
shale & lime	2900	lime lgt	4397
shale & lime shells	3020	lime grey hrd	4426
lime & shale	3070	sdv lime	4430
shale & lime shells	3163	lime	4437
shale & brkn lime	3256	Total Depth.	
lime	3393		
shale & brkn lime	3427	Cemented back to 4297	
shale & shells	3459		
lime	3500		
brkn lime & shale	3530		
shale	3560		
lime	3576		
shale & brkn lime	3624		
lime	3680		
sdv shale & lime shells	3740		
lime	3927		
Corr. 3927 equals	3929		
lime grey	3940		