


ATLANTIC REFG. CO.
Tritsch No. 1.

SEC.11 T.27 R.13 W
CSW SE

Total Depth. 4336'
Comm. 10-12-42 Comp. 12-27-42
Shot or Treated.
Contractor.
Issued. 2-6-43

County. Pratt



CASING:
8 5/8" 192' Cem.
5 1/2" 4331' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand	170	Shot with 1 qt glycerine
sand & red bed	225	from 4336-4335 12-23-42,
shale & shells	430	swbd about 15 Bbls
red bed & shale	712	formation wtr per hr
anhydrite	730	
red bed	850	
salt	950	Tops:
shale & shells	1850	Anhydrite 725
lime	1925	Florence Flint 2260
lime w/sand strks	2020	Marmaton 4120
sdv lime & shale	2155	Viola 4226
lime sdv	2200	Simpson shale 4323
shale & shells	2230	Simpson sand 4331
lime	2267	
lime brkn & shale	2320	
lime & shale	2400	
lime	2510	
brkn lime & shale	2535	
lime & shale	2705	
lime brkn	2745	
shale & shells	2765	
shale & lime	2975	
lime	2995	
shale & shells	3030	
lime	3116	
sdv lime & shale	3235	
lime	3415	
lime brkn & shale	3473	
lime	3490	
lime & shale	3540	
lime	3715	
lime & shale	3785	
lime	3820	
lime cherty	3895	
lime brkn	4065	
lime	4155	
lime cherty	4180	
shale w/chert strks	4195	
lime cherty	4245	
lime & chert	4290	
chert	4298	
lime & chert	4315	
lime & shale	4324	
shale	4329	

cored, rec 7' 4336
1' green Simpson shale
1' sdv shale & lime, no
shows
5' sand w/sh oil & gas
tight
Simpson 4336
Total Depth.

Perf. 12 shots 4334-4330
Perf. 24 shots 4332-4328