


ATLANTIC REFG.CO.
M.Tritsch No.1.

SEC.11 T.27 R.13 W
CNW SE

Total Depth. 4314'
Comm. 6-16-42 Comp. 7-2-42
Shot or Treated.
Contractor. Parker Drlg.Co.
Issued. 8-29-42 Rotary O-4314

County. Pratt



CASING:
8 5/8" 386' Cem.
5 1/2" 4304' Cem.

Elevation.

Production. Pot.831 B.Phy.

Figures Indicate Bottom of Formations.

surface sand	90	Sample Tops:	
sand, shale & sand, rock	200	Lansing	3769
sand rock	230	Viola	4212
shale & shells	393	Simpson	4294
rod bed	682	Simpson sand	4302
anhydrite	705		
shale & red bod	1010		
salt & shale	1195		
shale & shells	1250		
shale & lime shells	1595		
shale & lime shells	1800		
shale & shells	1940		
shale & lime	2100		
lime brkn	2185		
lime sdy	2215		
lime brkn	2300		
shale & lime	2405		
shale & shells	2510		
lime brkn	2610		
shale & shells	2735		
shale & lime shells	2810		
shale & shells	2915		
shale & lime	3090		
shale & shells	3180		
lime & shale	3300	chert	4217
lime w/shale strks	3380	chert w/shale	4230
shale & shells	3375	lime cherty	4235
lime sft & shale	3470	lime & shale	4254
lime & shale	3520	chert & lime	4280
lime sft & shale	3625	shale w/chert	4300
lime & shale	3792	core, shale	4304
lime w/shale strks	3845	core, sand	4310
lime	3864	core, sand w/some	
lime sft	3882	shale strks	4314
lime	3894		
lime sft	3896		
lime	3960	Total Depth.	
lime sft	3972		
lime	3994		
lime sft	4007	Producing area 4310-14	
lime	4075		
lime & shale	4120		
lime w/chert	4191		
lime & shale	4212		