

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


1 - 27 - 13W

MARYLYN OIL CO.
Jackson No. 1.

SEC.1 T.27 R.13W
CE $\frac{1}{2}$ NE NW

Total Depth. 4339'
Comm. 8-16-40 Comp. 9-5-40
Shot or Treated.
Contractor. Gerbrand-Pulse Oil & Drlg.Co.
Issued. 12-21-40

County. Pratt



CAS ING:
10 $\frac{3}{4}$ " 410'
7" 4206'
5 $\frac{1}{2}$ " liner 89'

Elevation.

Production. Dry


Figures Indicate Bottom of Formations.

shale	75
sand	95
sand & shale	390
shale red	515
chert & mica	525
red rock	630
anhydrite	690
red rock	720
shale & shells	1775
lime	2025
lime brkn	2060
shale & shells	2095
lime	2150
shale & shells	2330
lime brkn	2735
shale & shells	2950
lime brkn	3165
shale & shells	3212
lime	3460
shale & shells	3690
lime	3700
shale	3718
lime	3990
shale & shells	4065
lime	4110
shale	4112
lime cherty	4194
shale, shells, chert	4205
shale & shells	4216
Simpson sand (S.O.)	4232
shale	4236
sand wtr	4265
shale	4270
sand	4278
shale	4300
shale & iron pyrites	4316
Arbuckle lime (S.O.)	4339
Total Depth.	

Miss?

FORM 252-A 5M 2-40

Ft. from W. Line



Elev 1903

REPORT	
1940	
7/17	Location
7/25	Cellar.
8/2	R. Rig.
8/8	" "
8/14	" "
8/22	10" - 410' Drlg. 1010'
8/29	Neva 2500' Topeka 3198'
	Drlg. 3460'
9/5	Lansing 3721' SSO 3721-23 &
	3895-3911' Viola 4032'
	SO 4176-78' Simp. sand 4212'
	4221-31 Sat. Run 7".
9/12	7" - 4226' RUST.
9/19	Water 4241'
	TD 4312' SD.
9/26	Arb. 4316' T.D. 4339'
	125' water, 75' oil 8 hours.
10/3	C. O.
	4316 1923 2412
	OVER

1940

10/10 500 acid. No show.
11 shots 4227-31' No help.
SO & 700 water 7 hours.

10/17 T.D. 4342' No shows.

10/24 " " " "

10/31 " " " "

11/7 " " " "

11/14 " " " "

11/21 " " " "

11/27 " " " "

12/5 " " " "

12/11 Arb. 4316'

7" - 4226'

T.D. 4342'

Water.

ABANDONED
