


TUESDAY OIL CO.
B.C. Calbeck No. 1.

SEC. 1 T. 27 R. 13 W
C1W NE
660' fr WL 660' fr NL NE $\frac{1}{4}$

APR. 15-191-70713

Total Depth. 4347'
Comm. 9-10-42 Comp. 12-2-42
Shot or Treated.
Contractor. Hammum Drilg. Co.
Issued. 2-6-43 Rotary 4227
Cable 4347

County. Pratt



CASING:

10" 432'
7" 4223'
5" 4327'

Elevation.

Production. Temp. Abnd.

Figures Indicate Bottom of Formations.

clay	25
sand	135
red rock & sand	180
sand	230
red rock & sand	405
red rock & shells	735
anhydrite	780
sand	835
shale & shells	865
red rock, shale, shells	1060
shale & shells	1240
shale, shells, salt	1405
shale & shells	1495
shale, shells, anhydrite	1585
shale & shells	1725
anhydrite	1950
lime & shale	2070
sdv lime	2250
brkn lime & shale	2770
sand	2782
brkn lime & shale	2875
lime brkn	2905
lime sdv	2985
brkn lime & shale	3055
lime brkn	3195
lime	3435
brkn lime & shale	3460
sdv lime & shale	3500
brkn lime & shale	3520
brkn lime	3539
lime & shale	3711
lime	3765
lime cherty	3805
lime	3848
lime cherty	3871
lime	3980
lime & shale	4095
chert & lime	4119
shale	4145
chert	4210
shale & sand	4217
Core #1 Rec. 10'	
shaly sand green	4217-4224

Tops:
Lansing-K. C. 3711
Viola 4145-4210
Simpson shale 4210-24
Simpson sand 4224-27
Arbuckle 4327-47

sh oil 4224-27
rainbow sh oil 4227-27 $\frac{1}{2}$
slight sat. 4343-45
125' oil $\frac{1}{2}$ hr 4345
250' oil 3 hrs 4347
900' oil 21 hrs
swb 60' oil/hr, no
wtr 4 hrs
Acidized w/1000 Gals.
swb acid load thru
tbg, swb rainbow sh
oil & 120 BW, 12 hrs,
swbg 1200' off btm

sand, sh oil 4224-4227
sand 4232
4232 equals 4241 $\frac{1}{2}$ SIM
sand 4241 $\frac{1}{2}$
lime sdv 4251
sand 4281
shale 4304
4304 equals 4310 SIM
shale 4327
dolomite 4347
Total Depth.