

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

58610


THE ATLANTIC REFG.CO.
L.Rolf No. 1

SEC. 14 T. 27 R. 13 W.
CNE NW

Total Depth. 4355
Comm. 7-25-42 Comp. 8-25-42
Shot or treated.
Contractor. Parker Drilling Co.
Issued. 10-31-42

County Pratt.

Rotary.



CASING.

85/8" 358' cemented.
5 1/2" 4350' cemented.

Elevation

Production. Pot. 264 B.

Figures Indicate Bottom of Formations.

surface sand	66	limo and chart	3947
sand	160	limo	4005
red bed, shale and shells	375	limo soft	4014
red bed, shale & shells	740	limo	4139
anhydrite	775	limo and strks shale	4187
shale and shells	1050	cherty limo	4207
salt	1172	shale and shells	4254
shale and shells	1535	limo strks, chert and shale	4290
anhydrite and shale	1615	shale with chert	
shale and shells	1755	strks	4355
limo and shale	1875		
sand lime and shale	2050		
lime	2090		
sand	2115		
lime and strks sand	2150		
lime and strks sand	2240		
limo and shale	2715		
shale and shells	3015		
shale and lime	3240		
lime	3270		
lime soft	3300		
lime	3370		
limo and shale	3500		
lime	3650		
lime and shale	3815		
shale and limo	3865		
lime	3915		
lime and chert	3922		
lime	3948		
lime and chert	3952		
stuck drill pipe, cemented through drill pipe at 3102			
Set Whipstock at 3102			
shale and shells	3153- 3205		
shale	3270		
shale and shells	3340		
broken limo	3400		
limo and shale	3443		
shale	3530		
lime	3615		
limo and shale	3710		
limo with shale strks	3770		
limo and shale	3820		
lime	3905		
limo and strks shale	3940		

Total Depth.

Cored 4342-4355 Rec 4' shale
2' sand showing stain.

Drill stem test, open 1 hour, rec.
1920' fluid 240' mud, 330' drilling
water, 1350' oil.

SAMPLE TOPS.

Top Lansing 3815
Viola 4249
Simpson shale 4340
Simpson sand 4350