


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- W. J. COPPINGER
Farm- Apt No. 1

SEC. 30 T. 27 R. 13W
NW NW NE

Total Depth. 4455
Comm. 7-1-53 Comp. 7-23-53
Shot or Treated.
Contractor. Coppinger Drilling, Inc.
Issued. 10-3-53

County Pratt
KANSAS



Elevation. 1933 RB

Production. Pot. 216 BO & 10%
wtr.

CASING:

8 5/8 @ 400' w/ 250 sx cem.
5 1/2 @ 4140' w/ 150 sx cem.

Figures Indicate Bottom of Formations.

clay & sand	50
sand	90
red bed & sand	360
shale	400
red bed & sand	840
sand, red bed & shale	1300
shale	1520
shale & salt	1665
shale	1780
broken lime	1820
shale	1840
lime	1845
lime, shale & shells	1915
lime & shale	2025
shale & broken lime	2120
lime & shale	2225
lime	2275
sandy lime	2315
broken lime	2390
lime & shale	2465
shale & broken lime	2555
lime & shale	3355
lime	3520
lime & shale	3570
lime	3617
lime & shale	3737
shale	3800
lime & shale	3830
lime	3880
lime & shale	3920
lime	4174
shale & lime	4270
chert & lime	4300
lime & shale	4320
shale	4326
lime	4364
chert & junk	4383
lime	4396
chert & lime	4420
sand & chert	4430
lime & chert	4442
lime & shale	4455
Total Depth	

TOPS:

Heebner	3669
Brown lime	3820
Lansing	3840
Conglomerate	4266
Mississippi	4273
Kinderhook	4299
Viola	4326
Simpson shale	4409
Simpson sand	4415