

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY


503 East Murdock,

Wichita, Kansas

Company- W. J. COPPINGER et al.
Farm-Fitzsimmons No. 2SEC. 30 T. 27 R.13W
NW SE NWTotal Depth 4432 Whipstock hole 4130
Comm. 3-8-53 Comp. 3-29-53
Shot or Treated.
Contractor. Coppinger Drilling Co., Inc.
Issued. 7-4-53

County Pratt

KANSAS



CASING:

8 5/8 set at 374' w/ 250 sx cement
5 1/2 set at 4370' w/ 100 sx cement

Elevation. 1916 DF

Production. flow 423 bbls. +
4% wtr.

Figures indicate Bottom of Formations.

clay & sand	165	TOPS:	
red bed & shale	374	Anhydrite	817
red bed	460	Heebner	3654
sandy red bed	625	Brown lime	3807
red bed	817	Lansing KC	3826
anhydrite	845	Mississippi	4260
shale & shells	1600	Kinderhook	4288
shale & lime	1830	Viola	4306
lime	1925	Simpson	4396
lime & shale	2040		
lime	2100		
lime & shale	2265		
lime	2350		
lime & shale	3285		
lime & sand	3400		
lime	3547		
lime & shale	3755		
shale	3807		
Brown lime	3823		
Kansas City lime	3850		
lime	4151		
lime & shale	4253		
lime	4271		
chert	4288		
shale	4306		
chert	4325		
lime & chert	4355		
cherty lime	4396		
shale	4402		
dolomite & shale	4426		
lime & shale	4432		
Total Depth			

WHIPSTOCK HOLE--whipstock set at 3457'
Hole started angle 4 degrees bearing
East.Commenced 4-23-53
Completed 5-8-53

5 1/2 casing set at 4130 w/ 250 sx cement.

Cleaned out to whipstock
3050 to
cement & shale 3540
lime 3472
lime & shale 3657
shale 3805
lime 3847
Total Depth 4130