

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company-STERLING DRILLING CO. & C. F. HERTLEIN
Farm-Elliott "A" No. 3

SEC. 31 T. 27 R.13W
S/2 S/2 S/2

Total Depth. 4475 PBD 4460
Comm. 4-23-55 Comp. 6-2-55
Shot or Treated.
Contractor, Sterling Drilling Co.
Issued. 8-13-55

County Pratt

KANSAS



Elevation. 1912 BB

Production 1847 BOPD

CASING:

8 5/8 @ 359' w/ 225 sx cmt.
5 1/2 @ 4472' w/ 150 sx cmt.

Figures indicate Bottom of Formations.

sand & shale	360
shale & red bed	750
anhydrite	775
red bed & shale	1020
shale & shells	1815
lime	1925
shale & lime	2070
lime	2285
lime & shale	3445
lime	3665
lime & shale	3810
lime	4240
shale & lime	4300
shale & Viola chert	4335
lime	4375
shale & sand	4465
shale & lime	4475
Total Depth	4475

Plug back to 4460'

SCOUT TOPS:

Heebner	3645
Brown lime	3805
Lansing	3818
Mississippi	4275
Viola	4315
Simpson	4403

MICT, Drld cmt. to PBD 4460' perf
4399-4406, bailed 5 GW after 30 min.
Acid. w/ 500 gal. MCA, fraced w/
100 bbls. hvy crude & 4500# sand. ran
tbg. swbd. 18 bbls load oil & well
kicked off flowing @ rate 17 BOPD
for 5 hrs.