


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

Company- LION OIL CO.
Farm- Eyebanks No. 1

SEC. 8 T. 27 R. 11W
NE NE NE

Total Depth. 4646
Comm. 12-18-51 Comp. 1-11-52
Shot or Treated.
Contractor.
Issued. 4-19-52

County Pratt KANSAS



Elevation. 2007 RB

Production. 8,388,000 Gas

Figures indicate Bottom of Formations.

sand, shale lime & red beds	428	DST: 4492-4510, open 1 hr.
red beds & shale	586	rec. 35' SOCM 15 min BHP 70#
shale & shells	796	perf 44/4496-4504, 1000 acid -
red beds	1000	dry, perf 48/4367-83, 1,000
shale & shells	1960	acid, dry, PB 4200, perf 18/4181-87,
shale	2085	11/4190-94, dry, PB 4150, perf
lime & shale	3472	24/4139-45, 1,000 acid, swb wtr.,
lime	3535	w/slight show of gas. PB 4090
lime & shale & sand	3700	perf 23/4076-80, swab wtr., w/
lime & shale	3757	slight show of gas, PB 3950,
lime & sand	3870	perf 24/3916-26, wtr., w/slight
lime & shale	4045	show of gas, squeeze perforations
lime	4060	perf 40 jets/3929-36 1,000 acid
lime & shale	4129	1,750,000 CEG, swab 2 1/2 BFPH-95%
lime	4205	3,000 acid, flow 4 1/2 boph 5% bs
shale & lime	4311	& MCFG per day CH gauge 2500
cherty lime	4327	MCFGPD & 1 boph.
lime	4354	
chert & shale	4387	
lime	4418	
lime & shale	4445	
lime & shale & chert	4458	
chert & lime	4510	
lime	4538	
shale & lime	4563	
shale & sand strks	4610	
shale & lime	4646	
Total Depth		

Tops:
Brown Lime 3872
Lansing 3901
Miss. 4342
Viola 4436
Simpson 4531
Arbuckle 4630

DST: 3929-45, open 45 min.
gas 33 min. rec. 60' heavily
oil & gas cut mud & 90' muddy
oil & 80' muddy oil w/slight
wtr. cut & 10' wtr. 30 min.
BHP 1050#.

DST: 4045-60, open 45 min. rec.
25' very slightly oil & gas cut
mud, no BHP

DST: 4070-4108, open 1 hr. 20 min.
rec. 300' gas & 225' gas cut mud
w/slight trace of oil & 125' gas
cut salt wtr. 15 min BHP 1400#.
FP 215#

DST: 4130-45, open 45 min. rec.
30' very slightly oil cut mud.
15-min. BHP 1125#.

DST 4325-62, open 1 hr. rec. 700'
gas & 20' gas cut mud. no BHP