


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS CO.
Farm- Ewbank No. 1

SEC. 11 T. 27 R. 14W
SW SE NW

Total Depth. 4641
Comm. 12-14-54 Comp. 1-13-55
Shot or Treated.
Contractor. Buick Drlg, Inc.
Issued. 2-26-55

County Pratt
KANSAS



CASING:

13 3/8" 247' cem w/500 sx

Elevation. 1988 DF

Production. Dry

Figures Indicate Bottom of Formations.

soil sandy	70
sand	145
shale	160
sand, gravel	240
red bed	530
sand	600
red bed	890
anhydrite	915
shale, shells	1360
salt, shale	1510
shale, shells	1930
lime, shale	2065
lime	2215
lime, shale	2730
shale	2802
shale, lime	3540
lime	3590
lime, shale	3890
lime	3928
lime, shale	3960
lime	4021
lime, shale	4045
lime	4120
lime, shale	4144
lime	4170
lime, shale	4240
lime	4265
lime, shale	4388
chert	4390
chert, sand	4412
chert	4416
chert, lime, shale	4465
chert	4482
lime cherty, shale	4503
chert, lime, shale	4521
shale, lime	4633
lime	4641
Total Depth	

Tops:

Topeka	3096
Heebner	3694
Toronto	3712
Base Oread	3723
Douglas sand	3764
Brown Lime	3861
Lansing-K. C.	3888
Congl.	4340
Viola	4424
Simpson shale	4526
Simpson sand	4550
Arbuckle	4618

Schlumberger T. D. 4643