


FALCON-SEABOARD  
 Lemon No. 1

Soc. 32 T. 27 R. 14 W.  
 NW NE NW

Total Depth. 4765  
 Comm. 1-14-42 Comp. 2-24-42  
 Shot or Treated.  
 Contractor.  
 Issued. 3-14-42

County Pratt.



CASING

85/8" 881' cemented.

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

sand and shale	120	broken lime	3966
clay	162	shale and shells	3982
sand	184	lime	4054
red bed and shale	238	broken lime and	
sand and shells	387	shale	4071
red shale and shells	787	lime and chert	4132
sand and shale	840	lime	4205
shale blue	878	broken lime	4232
anhydrite	900	lime	4265
shale and shells	1135	broken lime	4315
salt	1507	lime	4324
shale and shells	1800	broken lime	4389
sdv shale	1950	lime and chert	4405
shale and lime	1960	broken lime	4434
lime	2170	sand and lime	4460
shale blue	2175	shale and lime	4481
lime	2207	sand chert and lime	4487
shale blue	2217	lime and chert	4493
lime	2234	lime	4514
shale	2236	lime and chert	4524
lime	2262	lime chert and	
shale and lime	2290	sand	4545
shale	2294	lime	4553
sdv lime	2337	lime and chert	4573
lime	2429	lime	4580
broken lime	2549	lime and chert	4606
shale and shells	2581	lime	4619
broken lime	2665	lime shale & chert	4662
sdv shale	2712	lime	4666
broken lime	2713	lime and shale	4715
lime	2785	lime	4765
shale	2836	Total Depth.	
shale and shells	3005		
sdv shale & shells	3070		
shale and shells	3215		
lime	3226		
shale and shells	3320		
broken lime	3336		
lime	3616		
lime and shale	3636		
broken lime	3668		
lime	3704		