

State

Kansas

County

Pratt

Company **Gordon Moraine (Norman, Okla.)** Well No. **1**

Farm Mary Crick

Survey

Block No.

Sec.

14

Twp. 27 S

Range 11 W

Co-Ord.

Elev.

1807¹ R/B

1805' D/F

W/2 NE/4 SE/4

Contr. - Garvey Drig.

A 6x6 grid map. The bottom-left 3x3 area is shaded and labeled "Park". A black dot is located at the intersection of the 4th column and 4th row.

Acresage Contribution:

25% - A. A. Seeligson, Jr.

12.5%-A. A. Seeligson, Sr.

12.5%-Ralph. Friedman

25% - Chicago Group

25% - Messman-Rinehart Oil

4100' Ls. test to be Comm.
on or before 9/1/61

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
5/5/61		Spud - 8-5/8" @ 307'
8/7	1700	Drlg.
8/8	2015	Drlg.
8/9	2310	Drlg. (Circ. for D.S.T.)
8/10	2785	Drlg.
D.S.T. #1 - 2253-2310'		- Op 1 hr., Rec.
		12' mud, no blow, BHP
		770-720#
	3624	Lansing

Date	Depth	692015
8/11	3185	Dr1g.
		D.S.T. #2 - 3726-56' - Op 30", Rec. 30'
		mud, BHP 440#
8/14		D.S.T. #3 (Ls.) 3807-12' - Op 30",
		Rec. 450' fluid,
		330- oil
		120' mdy wtr.)
		BHP 1290-1250#, GTS in 15",
		good blow
8/14	3860	R.T.D.
		5½" @ 3858'
		Perf.
		Perf. 3707-13', treated
		w/2000 gal. acid, set over†
		night, Fillup to within 1000
		of top, swbd. down to 2000'
		in 2 hrs.,
		Swbd. 50 B0 and 25 BW-2 hrs.