

State Kansas County Pratt

Company Messman-Rinehart Oil Company Well No. 91

Farm Park (QWWO)


Survey 1906 1011 - Comb. 104 52-30

Block No. _____ Sec. 14 Twp. 27 S Range 11 W

Co-Ord. _____ Elev. 1808 K/B

NW SE SW

M-R Rig



25% - Messman-Rinehart Oil Co
 50% - A. A. Seeligson, Jr.
 25% - Chicago Group

ORI - D.F. Moore, etal

CO to 4100' - Lansing
 on or before 3/15/59

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 990 Ft. from S. Line _____

1650 Ft. from W. Line _____ Ft. from E. Line _____

Date	Depth	
3-3-59		M.I.R.T.
3-4	1500	Drb
6:00 p.m.	3000	
	3620	Lansing (-1812)
	4130	COTD (Sj. Log)
3-6		Having difficulty getting
3-7		log run Fishing for sone
3-8		5 1/2" @ 4000' w/140 sx. cem., 3 gel., P.D. @ 4:20 p.m.

3/8/59

Date	Depth	692046
3-12-59		M.I.C.T.
		Perf. 3800-04 w/4 ^s ft.
		GTS in 2", 56 bbl. recovery
		on swb. down - no wtr.
		1st hr. - 5.01 BO natl.
		(34.2° - 12 hr. aver 5.78 BOPD)
3-13		Set overnight & filled up to 300'
3-14		Ran 2" tbg.
3-15		Treated w/500 gal. acid.,
		Went in @ 31 gal./min.,
		max. pressure 150#
		Swb. back & flow w/20 bbls.
		load not recovered
Choke 8/64		1st hr. - flow 24 BOPD
5/64		2nd hr. - flow 11 BO
8/64		3rd hr. - flow 24 BO
8/64 (opened up)		4th hr. - 22 BO
4/64		5th hr. - 10 BO in 45"
		Pressure: 100# tbg., 0# csg.
		Tank full - Comp. for 25-30
		BOPD
4-24		State Physical Potential:
		137 BOPD