

State Kansas County Pratt


Company Messman-Rinehart Oil Company Well No. 2

Farm Park

Survey

Block No. Sec. 14 Twp. 27 S Range 11 W

Co-Ord. Elev. 1810 K/B
1808 D/F



M-R Rig

25% - A. A. Seeligson, Jr.
12.5% - A. A. Seeligson, Sr.
12.5% - Ralph Friedman
25% - Chicago Group
25% - M-R Oil Co.
ORI - D.F. Moore, et al
4200' Miss. test

NOTE: Show Sketch of Lease and Well Location in Above Space

330

Ft. from N. Line

990

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
4-6-59		Location staked
		M.I.R.T. - Spud
		10-3/4" @ 300' w/200 sx. cem.,
		4 gel, 4 c.c., P.D. @ 8:00 a.m.
		4/10/59
4-12	1600	Drlg.
4-13	1955	Drlg. (#2 @ 1670)
4-14	2345	On bank w/#4 bit (#3 @ 1980)
4-15	2845	On bank w/#5 bit
4-16	3150	Dlr lq.

Date	Depth	
		692047
4-17	3465	Drig. 2"/ft. (#6 @ 3319)
4-20	3430	Heebner (-1620)
	3609	Brown Lime (-1799)
		Strapped DP
	3628	Lansing (-1818) 6' low
DST #1 - 3730	40	- Op 1 hr., Rec. 80' GCSW BHP 1110#
DST #2 - 3808	15	- Op 1 hr., C1 30", good blow throughout, Rec. 1000' gas, 90' mdy oil, 80' GCSW BHP 970#, FP 50-150#
4-21-DST #3 - 3901	47	- Op 1 hr., good blow throughout, Rec. 930' gas, 60' sli O&GCM, BHP 285-540#, FP 55-60#
4-22	4060	Drig. (#11 @ 3970)
	4099	Miss. (-2289)
	4115	R.T.D.
		4 $\frac{1}{2}$ " @ 4104' w/150 sx. cem., P.D. @ 1:15 a.m. 4/23/59
4-27		M.I.C.T. (Jetwell Log) Perf. 3942-46 w/4 ^s ft. SO & gas on gun
4-28		Treated w/1000 gal. acid,

State Kansas County Pratt

Company Messman-Rinehart Oil Company Well No. 2

Farm Park


Survey _____

Block No. _____ Sec. 14 Twp. 27 S Range 11 W

Co-Ord. _____ Elev. 1810 K/B

NW SW SW

M-R Rig



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

330

Ft. from N. Line

990

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		Swbd. 80 bbls. load & well
		dry, made $\frac{1}{2}$ BOPH (show gas
		& no wtr.)
		Set Plug @ 3850'
		Perf. 3812-16 w/4 ^s ft. (jet)
4-29		Swbd. 20 gal. oil & 5 $\frac{1}{2}$ BW
		in 30"
2-1		Treated w/500 gal. acid
		Swb. back 135 bbls. SW, then 8 BWph w/tr. oil
4-30		Set overnight and tested
		3 BO & 34 BW

[illegible]