

State Kansas County Pratt

Company Messman-Rinehart Oil Co. Well No. 3

Farm Park


Survey

Block No. Sec. 14 Twp. 27 S Range 11 W

Co-Ord. Elev. 1807' R/B  
1805' D/F

C. E/1 NW SE

M-R Rig



25% - A. A. Seeligson, Jr.  
12.5% - A. A. Seeligson, Sr.  
12.5% - Ralph Friedman  
25% - Chicago Group  
25% - Messman-Rinehart Oil Co.

3850' Ls. test

NOTE: Show Sketch of Lease and Well Location in Above Space

660 Ft. from N. Line Ft. from S. Line

Ft. from W. Line 330 Ft. from E. Line

Date	Depth	
9/19/61		Location staked
9/21		M.I.R.T.
9/22		Spud - 10-3/4' @ 274'
		w/230 sx. cem., 5 gel.,
		4 c.c., P.D. @ 4:15 p.m.
		9/23/61
9/25	1750	Drlg.
9/26	2080	Drlg.
9/27	2600	Drlg.

692048

Date	Depth	
9/28	2870	(On bank w/#5)
		Lost circ. - 2813'
		Full return - 2840'
9/29	3274	On bank w/#6 bit
	3427	Heebner (-1620)
		(visc., 33, wt. 10, wtr. loss
		D.S.T. #1 - 3801-13' - Op 1 hr., good bl., <sup>18)</sup>
		Rec. 2500' gas, 30' oil,
		85' hvy oil-cut mud, 95' oil
		& gas-cut salt wtr., BHP
		1197-1136#, FP 62-179#
		Temp 115°
		(2' higher than Crick zone offset to East)
		3611 - Brown Lime (-1804)
10/3	3954	D.D.
	3636	Lansing (-1829)
		D.S.T. #2 - 3903-54' - Op 1 hr., wk. bl.
		for 50", Rec. 12' mud,
		BHP 93-50#, FP 31-31#
10/4	3954	R.T.D.
		4 $\frac{1}{2}$ " @ 3861 w/50 sx. cem.,
		1 gel., P.D. @ 10 <sup>00</sup> a.m.
		10/4/61
10/12		M.I.C.T. (Ran Welex Radio- activity Log)

State Kansas County Pratt

Company Messman-Rinehart Oil Co. Well No. 3


Farm Park

Survey \_\_\_\_\_

Block No. \_\_\_\_\_ Sec. 14 Twp. 27 S Range 11 W

Co-Ord. \_\_\_\_\_ Elev. 1807' R/B  
1805' D/F

C. E/1 NW SE M-R Rig



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		Perf. 3810-14' w/4 <sup>s</sup> ft., Ran tbg to acidize
10/13		Treated w/500 gal. mud acid. Swb back load thru tbg.
(Swb tests)		1st hr. - 10 BF (50% wtr.)
		2nd hr. - 10 BF (55% wtr.)
		3rd hr. - 10 BF (3 BW & 7 BO)
		4th hr. - 10 BF (7 BW & 3 BO)
		P.O.P

