


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION CO.
Farm- Luther W. Stotts No. 1

SEC. 3 T. 27 R. 15W
C SE NE

Total Depth. 4663'
Comm. 8-14-57 Comp. 9-2-57
Shoal or Treated.
Contractor. Strata Drlg.
Issued. 12-7-57

County Pratt
KANSAS



CASING:
8 5/8" 326'

Elevation. 2060'

Production. Dry

Figures indicate Bottom of Formations.

sand and shell	300
red bed	1000
sand	1050
red bed and shale	1360
shale and shell	2055
lime and shale	3540
lime	3775
lime and shale	3865
lime	4290
lime and shale	4360
lime	4663
Total Depth	

TOPS:

Heebner (scout)	3578
Toronto (scout)	3779
Douglas (scout)	3788
Brown Lime	3910
Lansing-Kansas City	3934
Base Kansas City	4264
Penn. Sdy. Conglomerate	4367
Conglomerate cherty	4405
Viola	4459
Simpson Shale	4546
Simpson Sand	4557
Arbuckle	4649

Ran Electric log

DST #1 4055-4095', open 1 hr, shut in 20 min.
rec. 60' GCM, 210' SOCM, IBHP 1505#
FBHP 895#, FP 78-98#.

DST #2 4123-58, op. 1 hr., shut in 20 mins.
Rec. 65' MSW, BHP 1462-1240, FP 28-30#.

DST #3 4354-89, op 90 mins., shut in 20 mins.
gas to surface in 50 mins. (not enough
to gauge) 40' GCM, BHP 1170-1150#
FP 0#

DST #4 4378-99, op 35 mins., rec. 10' drilling
mud. shut in 20 mins. BHP 0#

DST #5 4405-50, op. 1 hr., shut in 20 mins.
rec. 40' mud with few speaks oil
BHP 0#.