

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING CO., INC.  
Farm- Jones No. 1

SEC. 13 T. 27 R. 15W  
SW SW SW

Total Depth. 4785  
Comm. 12-23-54 Comp. 1-11-55  
Shot or Treated.  
Contractor.  
Issued. 2-26-55

County Pratt  
KANSAS



8 5/8" CASING:  
223' cem w/225 sx.

Elevation. 2047 DF

Production. Dry

Figures Indicate Bottom of Formations.

sand	250
red bed	426
redbed,sand stks	950
anhydrite	980
shale, shells	1705
salt, shale, lime	1960
lime, shale	2065
lime	2160
shale, lime	3370
lime	3561
shale, lime	3975
lime	4270
lime, shale	4375
lime	4400
shale, sand	4429
chert,shale,lime	4459
shale, sand	4505
chert,lime,shale	4527
lime	4570
lime,shale,sand	4613
lime,shale	4658
shale, sand	4705
shale, lime	4735
arbuckle	4785
Total Depth	RTD

Tops:	
Heebner	3800
Douglas	3842
Brown Lime	3952
Lansing	3977
Base Kansas City	4289
Mississippian	4440
Kinderhook	4454
Viola Chert	4486
Solid Viola	4517
Simpson	4642
Arbuckle	4729

Drill Stem Test was found in the Miss. chert section, ind. on electric log to be from 4447-51, where 310,000 c.f.g. was gauged when the interval 4440-60 was tested. BHP 1200# Flowing press were zero.

Lansing: A drill stem test from 4050-75 Rec. only 265' of salt water, no shows of oil or gas.

Lower Penn. sect. (Marmaton)  
DST of this zone 4403-4429, Rec. only 33' of muc.