


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NATIONAL ASSOCIATED PETROLEUM CO.
Farm- Earlywine No. 1

SEC. 15 T. 27 R. 15W
SW SW NE

Total Depth. 4630'
Comm. 3-10-58 Comp. 3-21-58
Shot or Treated.
Contractor. Badger Drlg.
Issued. 4-26-58

County Pratt KANSAS



CASING:
8 5/8" 355' ccm w/300 sx.

Elevation. 2067' RB

Production. Dry

Figures Indicate Bottom of Formations.

substructure	5
cellar	9
surface soil & clay	65
sand	215
sand & shale	355
red bed w/shale strks	900
shale & shells	1125
shells & shale	1685
shale & shells	1990
shale & lime	2050
lime & shale	2160
shale & lime	2305
lime & shale	2445
shale w/lime strks	2565
lime & shale	2665
shale & lime	2790
shale & shells	2905
lime & shale	3070
shale & lime	3210
shale & shells	3260
lime & shale	3360
lime	3884
lime, shale, sand	3955
lime	4487
Miss. lime (Core #1)	4497
Miss. lime	4511
Core #1 Miss. lime	4517
Reaming	4517
Mississippi lime	4545
Kinderhook Shale	4595
Viola top - 4597	4617
Viola lime	4630
Total Depth	

TOPS: SCOUT

Heebner	3822
Toronto	3850
Douglas Shale	3895
Brown Lime	3984
Lansing	4006
Base Kansas City	4320
Cherokee Shale	4447
Mississippi	4492
Kinderhook	4530
Viola	4594