


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- OSAGE OIL & GAS CO., INC.
Farm- Thompson No. 1

SEC. 15 T. 27 R.15W
NW NW SE

Total Depth. 4820'
Comm. 3-6-57 Comp. 3-31-57
Shot or Treated.
Contractor. Prime Drilling Company
Issued. 2-15-58

County Pratt KANSAS



CASING:
8 5/8" 318' cem w/250 sx
5 1/2" 4612' cem w/150 sx

Elevation. 2064' RB

Production. 20 BOPD & 1,000,000
CFG

Figures Indicate Bottom of Formations.

sand	245
clay sand streaks	318
red beds & shale	1020
Anhydrite	1025
lime	1370
red bed & shale	1655
shale & lime	1995
lime	2325
lime & shale	2470
lime	2595
shale & lime	3265
lime	3580
lime & shale	3635
lime	3780
lime & shale	3995
lime	4481
lime cherty	4495
lime & shale	4510
chat	4550
chat & shale	4593
lime & chert	4617
lime	4641
lime, shale, sand chert	4670
chert & lime	4695
chert sand & lime	4718
shale, lime, chert, sand	4723
shale, sand, chert	4739
shale	4778
sand, shale, lime	4801
lime	4820-RTD
Total Depth	

TOPS: SCOUT

Heebner	3821
Brown Lime	3982
Lansing	4003
Conglomerate Sand	4481
Mississippi	4494
Kinderhook	4547
Kinderhook Sand	4580
Viola	4610
Simpson	4696
Arbuckle	4785