


WICHITA

OWWO

STATE KANSAS MAP NO. \_\_\_\_\_ SEC. 24-27S-18W WELL CLASS  
COUNTY KIOWA LOC. C S2 SE WFX \_\_\_\_\_ WFD \_\_\_\_\_  
INIT. \_\_\_\_\_ FIN. \_\_\_\_\_  
OPER. OIL PROPERTIES  
WELL 1 FARM THOMPSON  
POOL WILDCAT-1 1/2 MI N OF GREENSBURG(MISS-KH GAS)  
CONT. UNKNOWN GEOL. \_\_\_\_\_  
NO. NONE PROVINCE \_\_\_\_\_  
TR. 10-27-72 SPUD \_\_\_\_\_ COMP. \_\_\_\_\_  
TD \_\_\_\_\_ FORM \_\_\_\_\_ PBTD \_\_\_\_\_

PETROLEUM  
INFORMATION

| COMPLETION RECORD | Prod. Interval<br>Treatment | PRODUCING FM |  |  | FROM - TO |  |  | TREATMENT |  |  |
|-------------------|-----------------------------|--------------|--|--|-----------|--|--|-----------|--|--|
|                   |                             |              |  |  |           |  |  |           |  |  |
| Casing<br>Record  | Prod FM                     |              |  |  |           |  |  |           |  |  |
|                   | IP                          |              |  |  |           |  |  |           |  |  |
| Casing<br>Record  | SIZE                        | DEPTH        |  |  | SX        |  |  | SIZE      |  |  |
|                   |                             |              |  |  |           |  |  | DEPTH     |  |  |
|                   |                             |              |  |  |           |  |  |           |  |  |
|                   |                             |              |  |  |           |  |  |           |  |  |



(916 CENTURY PLAZA, WICHITA, KS)

OLD INFO: WAS PAN WESTERN PETROLEUM & SUN OIL, #1 WOODS,  
SPUD 11-16-63, 8-5/8" @ 303 W/275, GEOL-TOBY ELSTER, NO CORES,  
DST#1(CHER-MISS)4696-4720, OP2 HRS, GTS/4, GAUGE 1020 MCFGPD/  
15 & DEC TO GAUGE 434 MCFGPD/2 HRS, ISIP NONE, FP0, FSIP 1060/45  
DST#2(MISS)4720- 60, OP 2HR, GTS/13, TSTM, REC 130' MUD, ISIP  
1500/30, FP0, FSIP 1460/45, DST 3(KH)4767-4820, OP2 1/2 HR, BY PASS  
TOOL/8, INTERMIT BLOW, REC 60' SLI WTRY MUD, ISIP 1316/45, IEP  
100, FFP NONE, FSIP 1120/15, LOG, OTD 5136, DST4 STRD (MISS)  
4691-4727, OP 3 HRS, GTS/4, GAUGE 560 MCFGPD/5MIN, GAUGE 627  
MCFGPD/15, GA 627 MCFGPD/75, GA 560 MCFGPD/3 HRS, REC 420' HEAVY  
GAS CUT MUD + 30' GAS CUT WTRY MUD, ISIP 1574/45, IEP 167,  
FFP 167, FSIP 1467/45, D&A 12-17-63, OLD KB2156, DF2153, GR2151  
OLD KB LOG TOPS: HERRINGTON 2356, WINFIELD 2483, FORT RILEY 2516,  
WABAUNSEE SD3278, TARKIO 3356, HEEBNER 3996, CONT ON NEXT PAGE