

FEB 23

FEB
CONFIDENTIAL
CONFIDENTIALDRILL STEM TESTS:

DAVIS #3 - API No. 15-097-21,217
 225' S C NW SE
 Sec. ±5-27S-19W
 Kiowa County, Ks.

RELEASED

MAR 11 1994

FROM CONFIDENTIAL

-
- DST #1 - 4188'-4224'. 30-30-30-30 Rec. 90' gassy slightly oil cut mud.
 IF 33-49, FF 49-66. ISIP 232, FSIP 299. Temp. 110°.
- DST #2 - 4448'-65'. 60-60-60-60 Gas to surface in 60 min. - too small to
 measure. Rec. 240' clean oil, and 483' gassy, muddy oil. IF
 32-160, FF 144-225. ISIP 444, FSIP 928. Temp. 112°.
- DST #3 - 4782'-91'. 60-60-60-60 Gas to surface in 44 min. Rec. 10' gas
 cut mud. IF 32-48, FF 32-55. ISIP 1439, FSIP 1439. Temp. 118°.
- DST #4 - 4791'-4801'. 60-60-60-60 Gas to surface in 11 min. Rec. 110' mud.
 IF 48-73, FF 48-64. ISIP 1439, FSIP 1439. Temp 110°.
- DST #5 - 4801'-11'. 60-60-60-60 Gas to surface in 60 min. - too small to
 measure. Rec. 50' oil cut mud, 180' oil, 184' watery oil, and 837'
 water. IF 72-305, FF 305-495. ISIP 1471, FSIP 1477. Temp. 128°.