

ACO-1 BRENSING "B" #6 15-097-21361  
 135' S C W/2 SE NE Sec. 27-27S-19W  
 Kiowa County, Ks.

DRILL STEM TESTS

DST #1 - 4467'-82'. 30-30-30-30 Weak blow. Died in 30 min. Rec.  
 15' mud. IF 19-19, FF 29-29. ISIP 77, FSIP 48. Temp. 116°.

DST #2 - 4730'-65'. 60-60-60-60 Weak blow to strong blow first open.  
 Second open - strong blow to med. blow. Rec. 800' gas in pipe, 70'  
 GCM. IF 29-29, FF 39-39. ISIP 241, FSIP 173. Temp. 120°.

DST #3 - 4800'-10'. 60-60-60-60 Strong blow thruout both opens. Rec.  
 4800' gas in pipe, 70' GCM. IF 9-19, FF 19-38. ISIP 1172, FSIP 1182.  
 Temp. 119°.

DST #4 - 4810'-20'. 60-60-60-60 Strong blow for 2 min. first open, dec.  
 to med. blow second open. Rec. 3,000' gas in pipe 120' GCM. IF 9-38,  
 FF 9-48. ISIP 1076, FSIP 1096. Temp. 119°.

DST #5 - 4820'-35'. 60-60-60-60 GTS in 3 min. Rec. 300' gas & oil  
 cut water, 240' water. IF 48-96, FF 87-144. ISIP 1153, FSIP 1143.  
 Temp. 123°.