


WICHITA

STATE KANSAS MAP NO. _____ SEC. 35-27S-19W WELL CLASS DX
 COUNTY KIOWA LOC. C SW NE INIT. _____ FIN. _____
 OPER. PATE-DOMBAUGH & MARTIN EXPL
 WELL 1 FARM PLYLE
 POOL EINSEL (MISS-KH) ELEV. _____
GABBERT-JONES GEOL. _____
 NO. NONE PROVINCE _____
 FR. 11-30-72 SPUD. _____ COMP. _____
 TD. _____ FORM _____ PBDT _____

PETROLEUM INFORMATION



COMPLETION RECORD	Prod. Interval Treatment	PRODUCING FM	FROM - TO	TREATMENT		
Prod. FM IP						
Casing Record	SIZE	DEPTH	SX	SIZE	DEPTH	SX

(502 UNION CENTER, WICHITA, KS)

PTD. 5019' VIOLA GAS TEST

3 MI W & 3 1/2 MI N OF GREENSBURG, KS

TO START: 12-4-72- OLD INFO: WAS KENNETH RUPP, #1 PYLE

SPUD 7-26-65, 8" @ 617 W/425, DST #1(MISS) 4780-4832, OP5, SI45,

OP90, SI45, GTS/6, GA 240 MCFGPD/25, GA 260 MCFGPD/35, GA 280

MCFGPD/45, GA 280 MCFGPD/90, REC 90' GAS CUT MUD, ISIP 1556, IFP

52, FFP 73, FSIP 1514, OTD 5019, LOG, D&A 8-8-65, OLD KB 2248

OLD KB LOG TOPS: HEEBNER 4046, DOUGLAS SHALE 4086, BROWN LIME

4195, LANSING 4211, B/KANSAS CITY 4599, CHEROKEE SHALE 4726

MISS 4777, KINDERHOOK LM 4818, KINDERHOOK SD 4896, KINDERHOOK

LD 4902, VI 4994, LTD 5019, OLD KB SPL TOPS: BLAINE ANHY 610

B/BLAINE ANHY 625, CIMMARRON ANHY 1193, B/CIMMARRON ANHY 1219

MISS 4777,

NEW INFO: TO WASH DOWN & RETEST