

14-27-20W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NORTHERN NATURAL
Farm- Fralick "A" No. 1

SEC. 14 T. 27 R. 20W
C SW SW

Total Depth. 5413'
Comm. 3-21-60 Comp. 4-11-60
Shot or Treated.
Contractor. Stickle Drlg.
Issued. 8-17-63

County Kiowa
KANSAS



Elevation. 2300'

Production. 49 BOPD

CASING:

8 5/8" 557.59' cem w/400 sx.
5" 4950'

Figures Indicate Bottom of Formations.

sand	185	
red bed	300	
sand shale & shells	560	
shale, shells & red bed	720	
anhydrite	768	
shale & shells	1010	
red bed & shells	1255	
anhydrite	1295	
shale & shells	2365	
shale & lime	2465	
lime & shale	2545	
shale & lime	2685	
lime & shale	2910	
shale & lime	3055	
shale & lime streaks	3230	
shale & lime	3765	
lime & shale	3915	
chalky lime & shale	4027	
lime & shale	4150	
shale & lime	4221	
lime	4785	
lime & chert	4832	
?	4850	
chert	4935	
lime & chert	4960	
chert	4980	
chert & lime	5025	
shale & lime	5055	
lime	5100	
lime & shale	5153	
lime & chert	5179	
sand lime & chert	5210	
sand & lime	5243	
lime & sand	5318	
lime & chert	5375	
sand & lime & chert	5413	
Total Depth		
TOPS: SCOUT		
Chase	2452	Heebner 4058
		Brown Lime 4196
		Lansing 4204
		Marmaton 4626
		Cherokee 4741
		Mississippi Warsaw 4804
		Osage Chert 4843
		Viola 5042
		Simpson 5247
		Arbuckle 5331