

COMPLETION DATA SHEET

Lease EINSEL "A"
 Well No. 1 Sec. 21 T. 27S R. 20W
Kiowa Co., Kansas

DIVISION

FIELD

FRALICK WEST POOL

LOCATION

C SE NE

WELL PROFILE

TD

DRILL PIPE
4890'

LOG

ELEVATION

DATUM POINT (GRD-KB-DF)

KB

PBTD

DRILL PIPE
4890'

GAMMA-RAY

DATUM POINT ELEVATION

2295'

CASING DESIGN

SIZE	WEIGHT	GRADE	THREAD	COUPLING	MAKE	NO. JTS.	FOOTAGE	SACKS
8 5/8"							568'	285
4 1/2"	9 1/2#				Lone Star		4889'	125

PERFORATED INTERVAL	FORMATION	REMARKS
4871-72'	Mississippi	IP - 40 BOPD GOR 6750

COMMENTS:

2/20/66 SPUD

3/2/66 Cored 4860'-4890'. 9 1/2' good pay. DST #1

3/10/66 Acidized w/500 gal. XW-35. Acidized w/250 gal. XW-35

4/1/66 Well quit flowing. Hot oil did not work, high
paraffin buildup.

4/3/66 Used high pressure hot oiler. Ran new rods.

4/9/66 POP

4/15/66 Avg. 35 BPD.

12/6/83 Ran R-4 Packer. Acidized w/750 gal.

12/7/83 Pulled packer.

12/12/83 Ran R-4 Packer.

12/14/83 Acidized w/500 gal. of MOD202

12/15/83 Pulled Packer.

SUBMITTED BY

DATE

APPROVED BY

COMPLETION DATA SHEET

MULL DRILLING CO., INC.

Lease EINSEL 'A'
Well No. Sec. 21 T27S R20W
KIOWA Co., KSDIVISION _____ FIELD FRALICK WEST POOL LOCATION C SE NE

WELL PROFILE

TD	DRILL PIPE 4890	LOG	ELEVATION	DATUM POINT (GRD-KB-DF) KB
PBTD	DRILL PIPE 4890	GAMMA-RAY	DATUM POINT ELEVATION 2295	

CASING DESIGN

SIZE	WEIGHT	GRADE	THREAD	COUPLING	MAKE	NO. JTS.	FOOTAGE	SACKS
8 5/8"							568	285
4 1/2"	9 1/2#				LONE STAR		4889	125

PERFORATED INTERVAL	FORMATION	REMARKS
		IP - 40 BOPD GOR 6750
4871-72	MISS.	

COMMENTS:

3-2-66
SPUD 2-20-66. CORED 4860-4890. 9 1/2' good pay.
DST #1 → 3-2. Acidized w/500gals ^{XW-35} 3-10-66. Acidized w/250gals
XW-35. 4-1-66 - WELL QUIT FLOWING - HOT OIL DID NOT
WORK, HIGH PARAFFIN BUILDUP. 4-3 - USED HIGH PRESSURE HOT OILER -
RAN NEW ROOS. 4-9 - NEW HLT HIGH TORQUE ~~WATER~~ PUT
ON PUMP. 4-15 AUG 35 BPD. 12-6-83 - RAN R-A PACKER.
12-6-83 - ACIDIZED w/750gal. 12-7 pulled PACKER. 12-12 - RAN
R-A PACKER. 12-14 ACIDIZED w/500gal ^{MOD 202}. 12-15 pulled PACKER

SUBMITTED BY _____

DATE _____

APPROVED BY _____