

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

API No. 15

County

Number

Operator

Donald C. Slawson

Address

408 120 Building, Wichita, Kansas 67202

Well No.

Lease Name

1

Hicks 'C'

Footage Location

3300

feet from (S) line

660

feet from (W) line

Principal Contractor

Slawson Drilling Co.

Geologist

George Mueller

Spud Date

January 16, 1977

Total Depth

5060'

P.B.T.D.

5042'

Date Completed

January 26, 1977

Oil Purchaser

N/A


S. 29 T. 27 R. 21W E

Loc. C SW NW

County Ford

640 Acres

N



Locate well correctly

Elev.: Gr. 2350

DF. 2352 KB 2355

APR 07 1977

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$	8 5/8"	24#	405'	60/40 poz	300 sx	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas

Dry Hole

Well No.

Lease Name

1

Hicks 'C'

S 29 T 27 R 21W E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0- 120 Clay and Sand 120- 750 Shale and Sand streaks 750-1362 Shale 1362-1392 Anhydrite 1392-1480 Shale 1480-1788 Shale and Lime 1788-2349 Shale 2349-2380 Shale and Shells 2380-4940 Lime and Shale 4940-5060 Miss and RTD			LOG TOPS HEEB 4112 (-1757) BRN LM 4240 (-1885) LANS 4249 (-1894) B/KC 4636 (-2281) CHER 4813 (-2458) CG 4916 (-2561) MISS 4930 (-2575) LTD 5042	
DST #1 4878-4960, Pkr failed. DST #2 4850-4960, MISS, 30-30-45-60, GTS/? 12 MCF, Rec. 110' GCM, 65' SO&GCM, 155' O&GCM, IFP 110-170#, ISIP 1082#, FFP 140-160#, FSIP 1031# DST #3 4957-80, 30-45-45-60, WB, Rec. 195' GIP, 45' Tn SOCM, 60' MW, IFP 30-50#, ISIP 961#, FFP 60-70#, FSIP 901#				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

R.J. Thatcher

Signature

Petroleum Engineer

Title

February 3, 1977

Date

State Geological Survey
WICHITA, BRANCH

WELL LOG

15-057-20076

29-27-21W

OPERATOR: Donald C. Slawson
LEASE: #1 Hicks 'C'
C SW NW Sec. 29-27-21W
Ford County, Kansas
CONTRACTOR: Slawson Drilling Co., Inc.
COMMENCED: January 16, 1977
COMPLETED: January 26, 1977
CASING: Set 8 5/8" @ 405' w/300 sx
TOTAL DEPTH: 5060'

0- 120 Clay and Sand
120- 750 Shale and Sand Streaks
750-1362 Shale
1362-1392 Anhydrite
1392-1480 Shale
1480-1788 Shale and Lime
1788-2349 Shale
2349-2380 Shale and Shells
2380-4940 Lime and Shale
4940-5060 Miss and RTD

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

I, R. J. THATCHER, Of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Hicks 'C' well.


R. J. THATCHER

Subscribed and sworn to before me this 4th day of February, 1977.