

State Geological Survey

WICHITA BRANCH  
KANSAS DRILLERS LOG

IMPORTANT  
Kans. Geo. Survey request  
samples on this well.

15-057-20145

API No. 15 — 057 — 20,145

Operator

Texas Oil &amp; Gas Corp.

Address

300 - 200 West Douglas Wichita, Kansas 67202

Well No.  
#2Lease Name  
Young "F"

Footage Location

660 feet from (N) (S) line 1980 feet from (E) (W) line

Principal Contractor

H-30 Drilling

Geologist

Core Laboratories

Spud Date

9-13-79

Total Depth

5100'


P.B.T.D.

Date Completed

9-24-79

Oil Purchaser

N/A

640 Acres  
N

Locate well correctly

Elev.: Gr. 2323

DF KB 2331'

## CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Casing		8-5/8"	24#	591'		450	

## LINER RECORD

## PERFORATION RECORD

Top, ft. N/A	Bottom, ft. N/A	Sacks cement N/A	Shots per ft. N/A	Size & type N/A	Depth interval N/A

## TUBING RECORD

Size N/A	Setting depth N/A	Packer set at N/A		

## ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used			Depth interval treated
N/A			N/A

## INITIAL PRODUCTION

Date of first production P & A		Producing method (flowing, pumping, gas lift, etc.)				
		N/A				
RATE OF PRODUCTION PER 24 HOURS	Oil N/A	Gas bbis.	Water MCF	Gas-oil ratio bbis.		CFPB

Disposition of gas (vented, used on lease or sold) N/A			Producing interval(s) N/A		

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

### Operator

Texas Oil & Gas Corp.

**DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:**

**Well No.**

**Lease Name**

### Young "F"

### Dry Hole

S 34 T 27 R 21 E

## WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

**SHOW GEOLOGICAL MARKERS, LOGS RUN,  
OR OTHER DESCRIPTIVE INFORMATION.**

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Herington	2546	-215		
Cottonwood	3056	-725		
Onaga	3330	-999		
Wabaunsee	3342	-1011		
Heebner	4117	-1786		
Douglas	4155	-1824		
Lansing	4262	-1931		
Hertha	4606	-2275		
B/Kansas City	4685	-2354		
Mississippi	4917	-2586		
TD	5100			
<u>DST #1, 4906-55', (Miss.), w/results as follows:</u>				
IFP/30": 117-88#, GTS/15", 285 MCFD decr. to 86	MCFD			
ISIP/60": 1319#				
FFP/45": 88-88#, 100 MCFD decr. to 48	MCFD			
FSIP/90": 1124#				
Rec. 130' mud + 120' HOCM				
<u>DST #2, 4965-96', (Miss.), w/results as follows:</u>				
IFP/30": 100-346#, str blow				
ISIP/60": 1514#				
FFP/45": 436-670#, str blow				
FSIP/90": 1514#				
Rec. 1680' SW + 60' O & GCM				

**USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.**

**Date Received**

Hal Brown

HAROLD A. BROWN Signature

## District Exploration Manager

**Title**

September 25, 1979

Date \_\_\_\_\_

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 34 T. 27S R. 21W  
LOC. 660' FNL & 1980' FEL

FARM Young "F" NO. 2

COUNTY Ford

ROTARY TOTAL DEPTH 5,100'

COMM. September 13, 1979 COMP. September 24, 1979

CONTRACTOR H-30, INC. (Rig #3)

ISSUED October 10, 1979

CASING

10 3/4"

8 5/8" Set at 591' cemented w/450 sxs cement

ELEVATION 2,331' KB.

5 1/2"


4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Shale	592'
Red Bed, Shale and Sand	1,123'
Red Bed and Sand	1,591'
Shale	2,345'
Shale and Lime	2,975'
Lime and Shale	3,535'
Shale and Lime	3,730'
Lime and Shale	4,180'
Shale and Lime	4,347'
Lime and Shale	4,661'
Shale and Lime	4,775'
Lime and Shale	5,100'
Rotary Total Depth	5,100'

I hereby certify the above and foregoing to be  
a true and correct log of the above described  
well as shown by the drilling reports.

H-30, INC.

  
Dean Britting  
\_\_\_\_\_  
Dean Britting

State of Kansas } as:  
County of Sedgwick }

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 10th day of

October 1979.