


KANSAS CORPORATION COMMISSION

WELL RECORD

34-27-21

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



Lease Name: Weaver-Jones Well No. 1
 Well Located: Ford County
C-SW NW SEC 34 TWP 27S RGE 21W
 Operator: Halliburton Oil Producing Company
 Address: 117 Cameron Bldg., Oklahoma City, Oklahoma
 Elevation: Ground 2328 D.F. 2331 K.B. 2333
 Type Well: (Oil, gas, dry hole) Dry Hole

Casing set - Did not make a well

Drilling Commenced: 11-21 19 71 Drilling Completed: 12-4- 19 71
 Well Completed: 2-29 19 72 Total Depth 4952
 Initial Production: Salt water with gas show

Casing Record

Size: 8 5/8 Set at 567' Size: _____ Set at _____
 Size: 5 1/2 Set at 4951' Size: _____ Set at _____

Liner Record

Size: None Set from _____ To _____

Cementing

<u>Casing Size</u>	<u>Sacks</u>	<u>Type Cement and Additives</u>
<u>8 5/8</u>	<u>450</u>	<u>Pozmix</u>
<u>5 1/2</u>	<u>100</u>	<u>Pozmix - 18% salt</u>

Perforations

<u>Formation</u>	<u>Perforated Interval and Number Shots</u>
<u>Miss.</u>	<u>4930-4936 24 shots</u>
_____	_____
_____	_____

Electric Log Run (Show type log and depths covered)

Radiation-Guard Surface - T.D. _____

34-27-21

Show Drill Stem Tests,
Well Stimulation and
Production Tests

34-27-21w

Formation	Top	Bottom
Anhydrite	1334	1355
Queen Hill	3976	
Heebner	4125	
Toronto	4142	4157
Douglas	4160	
Brown Lime	4260	
Lansing	4268	
Swope	4574	
Hertha	4620	
Base K.C.	4700	
Marmaton	4735	4739
Cherokee	4837	4913
Conglomerate	4916	4926
Miss. Dolomite	4928	4934
Miss. Lime	4934	
T.D.	4852	

DST # 1 4906-4935
260' gassy oil, 140' frothy oil
180' muddy oil. Gas in $\frac{1}{2}$ hr. T.S.T.M.

DST # 2 4937-4952 30' mud.

DRILLER'S LOG

COMPANY: Halliburton Oil Producing Co., 117 Cameron Bldg., Okla. City, Okla.
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202
 LEASE: #1 Weaver-Jones
 LOCATION: c SW NW 34-27S-21W, Ford County, Kansas
 COMMENCED: November 21, 1971
 COMPLETED: December 4, 1971
 CASING: Set 8 5/8" Surface Casing @ 567'w/450 sacks cement
 Set 5 1/2" Casing @ 4951'w/100 sacks cement

		LOG TOPS	DEPTH
		SC	1334
		B SC	1354
		Q HILL	3976
		HEEB	4125
		TOR	4142
		DOUG	4160
		BN LM	4260
		LANS	4268
		SWOPE	4574
		HERTHA	4620
		BKC	4700
		CHER	4834
		CONG	4906
0-561	Shale - Sand	MISS DOL	4928
561-569	Blaine-Anhydrite	MISS LM	4934
569-1328	Shale & Shells	RTD	4952
1328-1359	Anhydrite	LTD	4953
1359-1780	Shale & Red Bed & Shells		
1780-2130	Shale & Salt Section		
2130-2655	Salt Section		
2655-2970	Lime		
2970-3725	Lime & Shale		
3725-3895	Lime & Shale (Topeka Section)		
3895-4240	Lime & Shale		
4240-4380	Lime & Shale - Brown Lime		
4380-4918	Lime		
4918-4952	Cong.-Miss.		