

JUL 24 1971

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

34-27-21W
CSE SW

YOUNG #1
SE SW Sec. 34-27S-21W
Ford County, Kansas

Commenced: June 6, 1971
Completed: June 22, 1971

OPERATOR: Halliburton Oil Producing Co.

all 2338 KB

4 PT Test 4,096,000

CF6PD,
NAT.
Miss. Prod 1315#

Depth		FORMATION	REMARKS
From	To		
0	30	Sand	Ran 11 joints of new 8 5/8" 20# casing set @ 358' w/ 275 sks HA5 Posmix P.D. @ 9:45 PM 6/6/71 Cement Cir. Job by Halco
30	358	Shale	
358	659	Red Bed	
659	1335	Shale and Shells	
1335	1370	Anhydrite	Log 20ft Stone Canal 1340 B. " " 1361 Log 20ft 3673
1370	1400	Shale	
1400	1755	Shale and Shells	
1755	2370	Shale and Lime	
2370	2883	Lime and Shale	Ran 156 Joints of used 4 1/2" Casing. Set @ 4956' - 1' off bottom Cemented w/100 sks Salt Sat Posmix 2% Gel - 12 1/2# Gilsonite per sack P.D. 2:30 PM 6/22/71 Job by Halliburton
2883	2935	Lime	
2935	3060	Shale and Lime	
3060	3190	Lime	
3190	4165	Lime and Shale	
4165	4340	Lime	
4340	4455	Lime and Shale	
4455	4957	Lime	
4957	TD		



I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the SE SW Sec. 34-27S-21W, Ford County, Kansas to the best of my knowledge and belief.

James S. Sutton II
James S. Sutton II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 28rd day of June, 1971, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.



Marjorie Hall
Marjorie Hall, Notary Public

My commission expires Nov. 29, 1971